

JUL 2017

10(3)

**RESOLUTION TO EFFECT URGENT REHABILITATION WORK TO
THE BURNSIDE HILL ROAD - RED HILLS DIVISION**

WHEREAS Burnside Hill is a Parochial Road and is in a state of disrepair.

AND WHEREAS the residents have extreme difficulties in accessing public transportation as a result of the condition of the road


AND WHEREAS this road negatively impact at least 1845 residents.

AND WHEREAS KSAMC does not have the requisite funds to effect repairs to the roads.

BE IT RESOLVED that the sum of Twelve Million, Six Hundred and Forty Thousand Dollars (\$12,640,000.00) as indicated in the attached estimate be granted from the Equalization fund to rehabilitate this road.

MOVED BY: CLLR : ROHAN HALL - Red Hills Division

SECONDED BY: CLLR: JERMAINE HYATT - Denham Town Division


KINGSTON & ST. ANDREW MUNICIPAL CORPORATION
Robert H.P. Hill, J.R.
CHIEF EXECUTIVE OFFICER

ksac roads

KINGSTON & ST. ANDREW MUNICIPAL CORPORATION
CHIEF ENGINEER'S DEPARTMENT

BILL OF QUANTITIES

DATE: MAY 25, 2017

DIVISION: RED HILLS

LOCATION: BURNSIDE HILL RD.


SUBJECT: ROAD REHABILITATION (670M X5M)

Item	Description	Qty	Unit	Rate	Total
A	Clean up and cart away silt, debris and other solid wastes from roadway and cart away spoils to an approved dump	1	sum	\$ 200,000.00	\$200,000.00
B	Provide tools, equipment and labour to scarify damaged surface and prepare formation as directed and cart away spoils to an approved dump	3150	m ²	\$ 300.00	\$945,000.00
C	150mm thick imported marl filling, spread, level and grade to fall and crossfall and well consolidated to receive asphaltic concrete	3150	m ²	\$ 800.00	\$2,520,000.00
D	Spread, roll and compact 38mm thick asphaltic concrete including prime coat applied to falls and crossfalls to the approval of the Engineer	3350	m ²	\$ 2,500.00	\$8,375,000.00
E	Construct kerb and channel	120	m	\$ 5,000.00	\$600,000.00
				TOTAL	\$12,640,000.00

Prepared by



KINGSTON & ST. ANDREW CORPORATION
CITY ENGINEER'S DEPT.


City Engineer