## CARROLL COUNTY WATER AUTHORITY FIG. 18 MAR. 2013 6" MIN NOTE: SIDE MOUNTED TEST COCKS SHALL NOT FACE VAULT WALL WITHOUT ADEQUATE CLEARANCE 18" MIN **PLAN VIEW** - 3" MIN. AIR GAP DRAIN PROVIDE SUPPORT BENEATH ASSEMBLY AS NECESSARY 12" MIN., 36" MAX. ADEQUATE DRAIN SHALL BE PROVIDED TO PREVENT WATER DAMAGE WHEN RELIEF VALVE DISCHARGES. MINIMUM DRAIN CAPACITY 60 GPM **PROFILE VIEW** REDUCED PRESSURE ASSEMBLY INDOOR INSTALLATION