

NEMA

TS 2-2003

SmartSensor Matrix

As contracted by Wavetronix, Tektronix Service Solutions performed NEMA testing in October 2010. The following report documents the results of the test and is unedited by Wavetronix.

Tester contact information:

Tektronix Service Solutions

6120 Hanging Moss Road
Orlando, Florida 32807

Tektronix

Service Solutions

6120 Hanging Moss Road, Orlando, Florida, 32807 (407) 678-6900, FAX (407) 671-0664

Customer: **WAVETRONIX**

P. O. No.: **PO0019046**

Job No.: **282245 - 001**

Order Quantity: **2 Systems**

Mfg. P/N

Customer P/N: **SS225, Click 112-114, 222, 204-205, 301**

Specification **Wavetronix Test Procedure (9/15/2010) & NEMA TS 2-2003**

Part Type:

Prepared By: **Eric Brentzel**

Date Prepared: **10/28/2010**

Reviewed By: 

Date Reviewed: **10-28-10**

CERTIFICATE OF COMPLIANCE

This is to certify that the referenced item was subjected to a testing program in accordance with your Procurement Document, as defined in the attached test plan. This plan specifies the test sequence, outlines the test conditions and provides a summary for each test.

Tektronix Service Solutions does not infer or imply that the test methods utilized in the body of this report have been granted suitability by the Defense Supply Center Columbus, (DSCC). A current listing of approved suitability methods is available upon request.


Mfr.: **WAVETRONIX**

Date Code: **-**

Accept: **2**
SYSTEMS

Reject: **0**

SEE ATTACHED DOCUMENTATION

Approved By: 

Date Approved: **10-30-10**

Page 2 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

INCOMING INSPECTION					10-15-10	E.B.
	Quantity	Model Number	Serial Number	Device Type		
	2	SS225	N/A	SmartSensor Radar		
	1	Click 112	N/A	2 Channel Card		
	1	Click 114	N/A	4 Channel Card		
	2	Click 222	N/A	Surge Suppressor		
	1	Click 202	N/A	2 Amp Power Supply		
	1	Click 204	N/A	4 Amp Power Supply		
	2	Click 301	N/A	Serial to Ethernet Conv.		

OPERATIONAL VERIFICATION TEST	<p>Documentation: Wavetronix Test Procedure (9/15/2010) & NEMA TS 2-2003, Paragraph 2.2.7.1 & 2.2.10</p> <p>Initial Setup and Verification: Connect the test unit AC input to an AC Power Source, programmable for both voltage and frequency output.</p> <p>Procedure:</p> <ol style="list-style-type: none"> 1. Apply 120V, 60Hz +/- 3Hz AC power to the AC inputs of the unit and verify system operation. 2. Vary input voltage from 89V to 135V, 60Hz +/- 3Hz AC power to the AC inputs of the unit and verify system operation. 3. Confirm proper operation of equipment by exercising operating and communication mode functions, as appropriate. <p>Test Observations: Two similarly configured WAVETRONIX SmartSensor Matrix systems were submitted for evaluation to the NEMA TS-2 Environmental Test Requirement.</p> <p>The first system consisted of the Click 222, 112, 202, 301 and SS225 while the second system consisted of the Click 222, 114, 204, 301 and SS225.</p> <p>The difference between the two configurations is power supply current rating (2 amp vs. 4 amp) and number of detector channels (2 channels vs. 4 channels). Noted differences aside, the configurations are outwardly identical in terms of setup and operation.</p> <p>At initial setup the WAVETRONIX SmartSensor Matrix equipment was found to operate properly across the prescribed range of AC Voltages and Frequencies.</p>	10-21-10	E.B.

Page 3 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

TRANSIENT TEST – (DC INPUT)	Documentation: Wavetronix Test Procedure (9/15/2010), Section 4.2 & NEMA TS 2-2003, Paragraph 2.8.1.3 Steps 1- 3, (I/O Terminals Sampled)	10-23-10	E.B.
	Conditions: Input Voltage Range: 10.8 – 26.5 VDC Transient Amplitude: 300 volts +- 5% Transient Polarity: Positive and Negative Pulse Width: 10 µs Source Impedance: 1,000 Ω Repetition: 5 Pulses /Polarity – 1 per second Procedure: 1. Apply nominal input power and configure unit to cycle, as appropriate. 2. Superimpose high-repetition noise transients on the DC input of the unit under test (“5” pulses at rate of “1” per second in each polarity). 3. Confirm that test unit continues to operate without malfunction during test.		
TRANSIENT TEST – (I/O TERMINALS)	Conditions: AC Input Voltage: 120V, 60Hz +- 3Hz DC Input Voltage Range: 10.8 – 26.5 VDC Transient Amplitude: 300 volts +- 5% Transient Polarity: Positive and Negative Pulse Width: 10 µs Source Impedance: 1,000 Ω Repetition: 5 Pulses /Polarity – 1 per second Procedure: 1. Apply nominal input power and configure unit to cycle, as appropriate. 2. With equipment configured per WAVETRONICS test procedure, apply transients to selected Input/Output (asserted and de-asserted as appropriate) of equipment under test, (“5” pulses at rate of “1” per second in each polarity). 3. Confirm that test unit continues to operate without malfunction during test.	10-23-10	E.B.
	Test Observations: The WAVETRONIX SmartSensor Matrix equipment system powered normally following application of the High-Repetition /Low-Repetition Transient test conditions. Communication with equipment and functional testing was performed without issue. The WAVETRONIX SmartSensor Matrix determined to be compliant to applicable NEMA TS-2, Transient Testing requirements, as performed in this section.		

Page 4 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

TRANSIENT TEST - (HIGH REPETITION NOISE TRANSIENTS)	Documentation: Wavetronix Test Procedure (9/15/2010), Section 4.2 & NEMA TS 2-2003, Paragraph 2.2.7.2 Steps 1-5 Conditions: Line Input Voltage: 120V, 60Hz +- 3Hz to AC inputs Transient Amplitude: 300 volts +- 5% Transient Polarity: Positive and Negative Pulse Width: 10 μ s Peak Power: 2,500 watts Duration: 5 Minutes min. (each polarity) Procedure: <ol style="list-style-type: none"> 1. Apply nominal input power and configure unit to cycle, as appropriate. 2. Superimpose high-repetition noise transients on the AC input of the unit under test (1 pulse every other cycle, moving uniformly over the full wave to sweep across 360 degrees of the line cycle once every 3 seconds.). 3. Confirm that test unit continues to operate without malfunction during the entire test. 	10-23-10	E.B.
	Conditions: Line Input Voltage: 120V, 60Hz +- 3Hz to AC inputs Transient Amplitude: 600 volts +- 5% Transient Polarity: Positive and Negative Repetitions: 10 (each polarity) Energy Source: Capacitor, oil-filled (10 microfarads) Procedure: <ol style="list-style-type: none"> 1. Apply nominal input power and configure unit to cycle, as appropriate. 2. Charge capacitor to prescribed voltage and discharge into the AC input of the unit under test (1 discharge every 10 seconds for a total of 10 discharges per polarity.). 3. Confirm that test unit continues to operate without malfunction. Test Observations: The WAVETRONIX SmartSensor Matrix equipment system powered normally following application of the High- Repetition /Low-Repetition Transient test conditions. Communication with equipment and functional testing was performed without issue. The WAVETRONIX SmartSensor Matrix determined to be compliant to applicable NEMA TS-2, Transient Testing requirements, as performed in this section.		

Page 5 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

TRANSIENT TEST – (NON-DESTRUCT TRANSIENT IMMUNITY)	Documentation: Wavetronix Test Procedure (9/15/2010), Section 4.2 & NEMA TS 2-2003, Paragraph 2.2.7.2 Steps 8-13	10-25-10	E.B.
	Conditions: Line Input Voltage: NO POWER APPLIED Transient Amplitude: 1000 volts +- 5% Transient Polarity: Positive and Negative Repetitions: 3 (each polarity) Energy Source: Capacitor, oil-filled (15 microfarads)		
	Procedure: <ol style="list-style-type: none"> 1. Apply NO POWER to unit. 2. Charge capacitor to prescribed voltage and discharge into the AC input of the unit under test, (1 discharge every 2 seconds for a total of 3 discharges per polarity.). 3. Upon completion of transient test, apply nominal “nominal” input power to unit and verify that device powers up and cycles through all functions normally. 		
	Test Observations: <p>The WAVETRONIX SmartSensor Matrix equipment system powered normally following application of the Non-Destruct Transient test conditions.</p> <p>Communication with equipment and functional testing was performed without issue.</p> <p>The WAVETRONIX SmartSensor Matrix determined to be compliant to applicable NEMA TS-2, Transient Testing requirements, as performed in this section.</p>		

Page 6 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

<p>LOW-TEMPERATURE - LOW-VOLTAGE TEST</p>	<p>Documentation: Wavetronix Test Procedure (9/15/2010), Section 4.3 & NEMA TS 2-2003 2.2.7.3 - 2.2.7.4 & Figure 2-1</p> <p>Conditions: Applied Input Voltage: 89V 60Hz +- 3Hz to AC inputs Temperature: -34°C Humidity: Uncontrolled Unit Status: Powered & operating in chamber</p> <p>Procedure:</p> <ol style="list-style-type: none"> 1. Beginning at ambient conditions, set input voltage to specified level and confirm correct operation. 2. With unit operating, ramp chamber temperature to -34°C at a rate not exceeding 17°C per hour. 3. Allow unit to operate for a minimum of 5 hours before exercising functions to determine that unit is operable. 4. Remove power from unit for a minimum of 5 hours 5. Restore power to unit and perform Functional /Operational tests as applicable. 	10-27-10	E.B.
	<p>Conditions: Applied Input Voltage: 135V 60Hz +- 3Hz to AC inputs Temperature: -34°C Humidity: 18% (not to exceed 95% as temperature "ramps" to +74°C) Unit Status: Powered & operating in chamber</p> <p>Procedure:</p> <ol style="list-style-type: none"> 1. With unit stabilized at -34°C, set input voltage to specified level and confirm correct operation. 2. Allow unit to operate for a minimum of 1 hour then exercise functions to determine that unit is operable. 3. Perform Functional /Operational tests as applicable. 4. Confirm that test unit functions normally in all modes. <p>Test Observations: The WAVETRONIX SmartSensor Matrix equipment system performed properly while operating with the specified "static" low-temperature and low/high voltage conditions applied.</p> <p>The WAVETRONIX SmartSensor Matrix determined to be compliant to applicable NEMA TS-2, Low-Temperature testing requirements, as performed in this section.</p>		

Page 7 of 29		WAVETRONIX	282245	001
TASK	CONDITIONS	Date Completed	Operator Stamp	
HIGH-TEMPERATURE - HIGH-VOLTAGE TEST	Documentation: Wavetronix Test Procedure (9/15/2010), Section 4.3 & NEMA TS 2-2003 2.2.7.5 – 2.2.7.6 Conditions: Applied Input Voltage: 135V 60Hz +- 3Hz to AC inputs Temperature: +74°C Humidity: 18% Unit Status: Powered & operating in chamber Procedure: <ol style="list-style-type: none"> 1. With unit operating, ramp chamber temperature to +74°C at a rate not exceeding 17°C per hour with humidity at 18%. 2. Maintain temperature and humidity conditions and allow unit to operate for a minimum of 15 hours before exercising functions to determine that unit is operable. 3. Confirm that test unit functions normally in all modes. 	10-28-10	E.B.	
	Conditions: Applied Input Voltage: 89V 60Hz +- 3Hz to AC inputs Temperature: +74°C Humidity: 18% Unit Status: Powered & operating in chamber Procedure: <ol style="list-style-type: none"> 1. With unit stabilized at +74°C, set input voltage to specified level and confirm correct operation. 2. Perform Functional /Operational tests as applicable to confirm proper operation. 3. Ramp chamber temperature to room ambient at a rate not exceeding 17°C per hour. 4. Allow unit to stabilize at ambient condition for one hour before removing from chamber. 5. Confirm that test unit functions normally in all modes. Test Observations: The WAVETRONIX SmartSensor Matrix equipment system performed properly while operating with the specified "static" high-temperature and high/low voltage conditions applied. The WAVETRONIX SmartSensor Matrix determined to be compliant to applicable NEMA TS-2, High-Temperature testing requirements, as performed in this section.	10-28-10	E.B.	

Page 8 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

VIBRATION - (RESONANT SEARCH)	Documentation: Wavetronix Test Procedure (9/15/2010), Section 4.1 & NEMA TS 2-2003 2.2.8.1 – 2.2.8.4 Conditions: Frequency Range: 5 - 30Hz Displacement Level: 0.015 inch DA Number of Sweeps: 1 Sweep Duration: 12.5 minutes Number of axis: 3 (X, Y & Z) Procedure: <ol style="list-style-type: none"> 1. Verify accelerometer operation 2. Attach unit to the vibration table. 3. Note resonant frequencies in a given plane and record the most severe 4. If resonances found are equally severe, record each frequency. 5. If no resonant frequency is found for a given plane, record 30Hz. 	10-29-10	M.L.
	VIBRATION - (ENDURANCE TEST)		
	Conditions: Frequency Range: 5 - 30Hz (Per results of Resonant Search) Acceleration Level: 0.5g Dwell Duration: 1 hour per each axis Number of axis: 3 (X, Y & Z) Procedure: <ol style="list-style-type: none"> 1. Verify accelerometer operation 2. Attach unit to the vibration table. 3. Vibrate test unit in each plane for prescribed period of time. 4. If more than one resonant frequency was recorded, the test period shall be divided equally between resonant frequencies. 5. If no resonant frequencies were noted the test shall be performed at 30Hz. Details: <ul style="list-style-type: none"> • Examine for physical damage attributable to vibration testing. • Verify that the unit powers up and is able to function normally in all modes. Test Observations: <p>No Resonant Frequencies were noted in the frequency range of applied vibration. The Endurance test was consequently performed at the single frequency of 30Hz. Test units operated normally following exposure to the applied vibration test frequencies and levels.</p>	10-29-10	M.L.

Page 9 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

SHOCK	Documentation: Wavetronix Test Procedure (9/15/2010), Section 4.4 & NEMA TS 2-2003 2.2.9.1 – 2.2.9.4	10-29-10	M. L.
	Conditions:		
	Shock Amplitude: 10 g's		
	Shock Duration: 10 msec		
	Waveform: Half-sine		
	Number of axis: 3 (X, Y & Z)		
	Number shocks per Orientation: 2 (one in each direction)		
	Total Shocks: 6		
	Procedure:		
	1. Verify accelerometer operation 2. Attach unit to the shock table. 3. Shock test unit in each plane in accordance with test requirement.		
Details:			
• Examine for physical damage attributable to shock testing. • Verify that the unit powers up and is able to function normally in all modes.			
Test Observations:			
Post-shock test evaluation revealed no physical or cosmetic damage to the test units. Subsequent electrical testing showed proper operation of the WAVETRONIX SmartSensor Matrix equipment system.			
The WAVETRONIX SmartSensor Matrix determined to be compliant to applicable NEMA TS-2, Vibration and Shock testing requirements, as performed in this and preceding section.			


TASK

CONDITIONS

Date
CompletedOperator
Stamp

WAVETRONIX - 282245

— Ambient Temperature (°C) — Ambient Humidity(%rh)



Temperature Humidity Profile

Page 11 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: RESONANT SEARCH - X-AXIS

Serial Number:

Project File Name: NEMA RES SEARCH.prj

Profile Name: NEMA Resonant Search


29, 2010 09-01-00

Test Type:

Swept Sine

Run Folder:

.RunDefault Oct



Level: 100 % Full Level Time: 00:12:30 Sweep Type: Logarithmic
Frequency: 5.000975 Hz Time Remaining: 00:00:00 Sweep Rate: 0.414 Oct/Min

Data saved at 09:13:47 AM, Friday, October 29, 2010

Report created at 09:13:49 AM, Friday, October 29, 2010

Page 12 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: ENDURANCE DWELL - X-AXIS

Serial Number:

Project File Name: NEMA ENDURANCE.prj

Profile Name: NEMA Resonant Search


29, 2010 09-15-56

Test Type:

Swept Sine

Run Folder:

.RunDefault Oct



Level: 100 % Full Level Time: 01:00:00 Sweep Type: Logarithmic
Frequency: 30.000000 Hz Time Remaining: 00:00:00 Sweep Rate: 1 Oct/Min

Data saved at 10:19:40 AM, Friday, October 29, 2010


Report created at 10:19:41 AM, Friday, October 29, 2010

Page 13 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: SHOCK - X-AXIS
Serial Number:
Project File Name: NEMA SHOCK 10G.prj
Profile Name: 10gn 10mSec
10-21-06

Test Type: Classical Shock

Run Folder: .\RunDefault Oct 29, 2010



Level: 100 %
Block Size: 2048
Elapsed Pulses: 9

Frame Time: 0.200000 Seconds
Control Peak: 9.967143
Control RMS: 1.969124
Full Level Elapsed Pulses: 1

dT: 0.000098 Seconds
Demand Peak: 10.000000
Demand RMS: 1.968571
Remaining Pulses: 0

Pulse Type: Half Sine
Amplitude: 10.000000
Pulse Width: 10.000000 ms

Data saved at 10:21:26 AM, Friday, October 29, 2010
Report created at 10:21:26 AM, Friday, October 29, 2010

TASK

CONDITIONS

Date
CompletedOperator
Stamp

DUT: SHOCK - X-AXIS NEG

Serial Number:

Project File Name: NEMA SHOCK 10G.prj

Profile Name: 10gn 10mSec


10-22-03

Test Type:

Classical Shock

Run Folder:

.RunDefault Oct 29, 2010



Level:	100 %	Block Size:	2048	Elapsed Pulses:	9	
Frame Time:	0.200000 Seconds	Control Peak:	10.015448	Control RMS:	1.967827	Full Level Elapsed Pulses: 1
dT:	0.000098 Seconds	Demand Peak:	10.000000	Demand RMS:	1.968571	Remaining Pulses: 0
Pulse Type:	Half Sine	Amplitude:	10.000000	Pulse Width:	10.000000 ms	

Data saved at 10:22:26 AM, Friday, October 29, 2010 Report created at 10:22:27 AM, Friday, October 29, 2010

Page 15 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: RESONANT SEARCH - Y-AXIS

Serial Number:

Project File Name: NEMA RES SEARCH.prj

Profile Name: NEMA Resonant Search


29, 2010 11-15-11

Test Type:

Swept Sine

Run Folder:

.RunDefault Oct



Level: 100 % Full Level Time: 00:12:30 Sweep Type: Logarithmic
Frequency: 5.000719 Hz Time Remaining: 00:00:00 Sweep Rate: 0.414 Oct/Min

Data saved at 11:30:15 AM, Friday, October 29, 2010


Report created at 11:30:16 AM, Friday, October 29, 2010

Page 16 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: ENDURANCE DWELL - Y-AXIS
Serial Number:
Project File Name: NEMA ENDURANCE.prj
Profile Name: NEMA Resonant Search
29, 2010 11-30-51

Test Type: Swept Sine

Run Folder: .\RunDefault Oct



Level: 100 %
Full Level Time: 01:00:00
Sweep Type: Logarithmic

Frequency: 30.000000 Hz
Time Remaining: 00:00:00
Sweep Rate: 1 Oct/Min

Page 17 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: SHOCK - Y-AXIS POS

Serial Number:

Project File Name: NEMA SHOCK 10G.prj

Profile Name: 10gn 10mSec


12-34-59

Test Type:

Classical Shock

Run Folder:

.RunDefault Oct 29, 2010



Level:	100 %	Block Size:	2048	Elapsed Pulses:	9
Frame Time:	0.200000 Seconds	Control Peak:	9.994732	Control RMS:	1.978429
dT:	0.000098 Seconds	Demand Peak:	10.000000	Demand RMS:	1.968571
Pulse Type:	Half Sine	Amplitude:	10.000000	Pulse Width:	10.000000 ms

Full Level Elapsed Pulses: 1
Remaining Pulses: 0

Data saved at 12:35:19 PM, Friday, October 29, 2010 Report created at 12:35:19 PM, Friday, October 29, 2010

TASK	CONDITIONS	Date Completed	Operator Stamp
------	------------	----------------	----------------

DUT: SHOCK - Y-AXIS NEG

Serial Number:

Project File Name: NEMA SHOCK 10G.prj

Profile Name: 10gn 10mSec


Test Type:

Classical Shock

Run Folder:

.\RunDefault Oct 29, 2010

12-35-52



Level:	100 %	Block Size:	2048	Elapsed Pulses:	9		
Frame Time:	0.200000 Seconds	Control Peak:	10.029775	Control RMS:	1.976385	Full Level Elapsed Pulses:	1
dT:	0.000098 Seconds	Demand Peak:	10.000000	Demand RMS:	1.968571	Remaining Pulses:	0
Pulse Type:	Half Sine	Amplitude:	10.000000	Pulse Width:	10.000000 ms		


Data saved at 12:36:08 PM, Friday, October 29, 2010 Report created at 12:36:08 PM, Friday, October 29, 2010

Page 19 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: RESONANT SEARCH - Z-AXIS
Serial Number:
Project File Name: NEMA RES SEARCH.prj
Profile Name: NEMA Resonant Search
29, 2010 12-58-38

Test Type: Swept Sine

Run Folder: .\RunDefault Oct



Level: 100 %
Full Level Time: 00:12:30
Sweep Type: Logarithmic

Frequency: 5.001230 Hz
Time Remaining: 00:00:00
Sweep Rate: 0.414 Oct/Min

Data saved at 01:12:40 PM, Friday, October 29, 2010

Report created at 01:12:41 PM, Friday, October 29, 2010

Page 20 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: ENDURANCE DWELL - Z-AXIS

Serial Number:

Project File Name: NEMA ENDURANCE.prj

Profile Name: NEMA Resonant Search


29, 2010 13-14-07

Test Type:

Swept Sine

Run Folder:

.\\RunDefault Oct



Level: 100 % Full Level Time: 01:00:00 Sweep Type: Logarithmic
Frequency: 30.000000 Hz Time Remaining: 00:00:00 Sweep Rate: 1 Oct/Min

Data saved at 02:14:20 PM, Friday, October 29, 2010

Report created at 02:14:20 PM, Friday, October 29, 2010

Page 21 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

DUT: SHOCK - Z-AXIS POS

Serial Number:

Project File Name: NEMA SHOCK 10G.prj

Profile Name: 10gn 10mSec


14-15-25

Test Type:

Classical Shock

Run Folder:

.RunDefault Oct 29, 2010



Level:	100 %	Block Size:	2048	Elapsed Pulses:	9
Frame Time:	0.200000 Seconds	Control Peak:	10.057504	Control RMS:	1.973414
dT:	0.000098 Seconds	Demand Peak:	10.000000	Demand RMS:	1.968571
Pulse Type:	Half Sine	Amplitude:	10.000000	Pulse Width:	10.000000 ms

Data saved at 02:15:58 PM, Friday, October 29, 2010

Report created at 02:15:58 PM, Friday, October 29, 2010

Full Level Elapsed Pulses: 1
Remaining Pulses: 0

TASK	CONDITIONS	Date Completed	Operator Stamp
------	------------	----------------	----------------

DUT: SHOCK - Z-AXIS NEG

Serial Number:

Project File Name: NEMA SHOCK 10G.prj

Profile Name: 10gn 10mSec


Test Type:

Classical Shock

Run Folder:

.\RunDefault Oct 29, 2010

14-16-16




Level:	100 %	Block Size:	2048	Elapsed Pulses:	9	
Frame Time:	0.200000 Seconds	Control Peak:	10.041819	Control RMS:	1.970819	Full Level Elapsed Pulses: 1
dT:	0.000098 Seconds	Demand Peak:	10.000000	Demand RMS:	1.968571	Remaining Pulses: 0
Pulse Type:	Half Sine	Amplitude:	10.000000	Pulse Width:	10.000000 ms	

Data saved at 02:16:44 PM, Friday, October 29, 2010 Report created at 02:16:44 PM, Friday, October 29, 2010


Page 23 of 29		WAVETRONIX	282245	001
TASK	CONDITIONS		Date Completed	Operator Stamp




WAVETRONIX SmartSensor Matrix equipment, Click 112, 204, 222 & 301




Page 24 of 29		WAVETRONIX	282245	001
TASK	CONDITIONS		Date Completed	Operator Stamp



WAVETRONIX SmartSensor Matrix equipment, Click 114, 202, 222 & 301



Page 25 of 29		WAVETRONIX	282245	001
TASK	CONDITIONS		Date Completed	Operator Stamp




WAVETRONIX SmartSensor Matrix, SS225 Sensor

TASK


CONDITIONS

Date
CompletedOperator
Stamp

WAVETRONIX SmartSensor Matrix equipment configured for Temperature /Humidity.



TASK	CONDITIONS	Date Completed	Operator Stamp
------	------------	----------------	----------------



WAVETRONIX SmartSensor Matrix equipment, configured for Vibration and Shock testing in X, Y & Z orientations.



TASK	CONDITIONS	Date Completed	Operator Stamp
------	------------	----------------	----------------



WAVETRONIX mounted to LDS V8-440 Vibration Simulation System.

Page 29 of 29		WAVETRONIX		282245	001
TASK	CONDITIONS			Date Completed	Operator Stamp

USAGE LOG	All Equipment Station Logs Completed.				10-24-10	E.B.
	Manufacturer	Model # / Function	Asset #	Cal. Due		
	Envirotronics	SH27-C	83-6402	10/14/11		
	LDS	V8 / Shaker	83-1120PT	11/5/10		
	Kistler	8704B500M1 /Accel	83-6365	1/4/11		
	Dytran	3023A / Accel	83-6374	3/31/11		
	Dytran	3023A / Accel	83-6393	4/19/11		
	Dytran	3023A / Accel	83-6395	4/19/11		
	Pacific Power	110-HE / AC Pwr. Sup.	83-6099	4/21/11		
	Tektronix	TDS3064B /Oscope	83-6340	10/7/11		
	HP	6634 /Power Supply	83-6218	3/5/11		
	Fluke	80K-40 HV /HV Probe	83-5419	3/19/11		
	Fluke	87 Series IV /DMM	83-6256	12/21/10		

PACK	Use original container or equivalent One copy of test plan.		
SHIP TO:	WAVETRONIX. 78 EAST 1700 SOUTH BUILDING B PROVO, UT 84606		
SHIP VIA:			