

W W W . M C C R A K . C O M

111 ZENWAY BLVD., UNIT 4, VAUGHAN, ONTARIO, L4H 3H9
TEL: 416.675.0160 FAX: 905 851.1722
office@mccrak.com

1271 DENISON ST., UNIT 45, MARKHAM, ONTARIO, L3R 4B5
TEL: 905.470.0160 FAX: 905.475.6371

denison@mccrak.com

McMASTER INNOVATION PARK - COLABORATORY No. 110

175 LONGWOOD RD. S., HAMILTON, ONTARIO, L8P 0A1 office@mccrak.com

MG4842 MARCH 2021

GEOHYDROLOGY ASSESSMENT PIER 27 PHASE THREE 25 & 35 QUEENS QUAY EAST TORONTO, ONTARIO

DISTRIBUTION:

1 COPY (electronic) PIER 27 TORONTO (NORTHEAST) INC.

1 COPY McCLYMONT& RAK ENGINEERS, INC.

PREPARED FOR:

PIER 27 TORONTO (NORTHEAST) INC. 56 THE ESPLANADE, SUITE 308 TORONTO, ONTARIO M5E 1A7

TABLE OF CONTENTS

| Item | | Page |
|---|---|-------------|
| 1.0 | INTRODUCTION | 1 |
| 1.1 1.2 1.3 1.4 1.5 | SCOPE OF WORK SITE DESCRIPTION PROPOSED DEVELOPMENT PROPERTY OWNERSHIP REVIEW OF PREVIOUS REPORTS | |
| 2.0 | HYDROGEOLOGICAL CONDITIONS | 4 |
| 2.1 2.2 2.3 2.4 | Physical Setting Topography Regional Geology and Hydrogeology Local Geology and Hydrogeology | 4 4 |
| 3.0 | SCOPE OF INVESTIGATION | 6 |
| 3.1 3.2 3.3 3.4 3.5 | OVERVIEW OF SITE INVESTIGATION MONITORING WELL INSTALLATION ELEVATION SURVEYING GROUNDWATER SAMPLING GROUNDWATER ANALYSIS | 6 6 7 |
| 4.0 | INVESTIGATION RESULTS | 8 |
| 4.1 4.2 4.3 4.4 | GEOLOGY GROUNDWATER LEVEL MONITORING GROUNDWATER QUALITY GROUNDWATER DISCHARGE ASSESSMENT | 9 10 |
| 5.0 | REVIEW AND EVALUATION | 11 |
| 5.1 5.1.1 5.2 5.2.1 5.3 5.4 5.5 | TEMPORARY DEWATERING ASSESSMENT NUMERICAL ANALYSIS PERMANENT FOUNDATION DRAIN FLOW RATES NUMERICAL ANALYSIS MECP PERMIT TO TAKE WATER REQUIREMENT TORONTO WATER DISCHARGE PERMIT REQUIREMENTS. ENVIRONMENTAL PROTECTION | 131415 |
| 6.0 | CONCLUSIONS AND RECOMMENDATIONS | 17 |
| 7.0 | REFERENCES | 20 |
| 8.0 | STATEMENT OF LIMITATIONS | 21 |
| 9.0 | CLOSURE | 22 |

FIGURES

Drawing No. 1 Borehole Location Plan

Drawing No. 2 Private Water Drainage System

TABLES

| Table 1 | Construction Details and Elevation of Monitoring Wells |
|---------|---|
| Table 2 | Groundwater Analytical Results – City of Toronto Sewers By-Law Discharge Criteria |
| Table 3 | Groundwater Monitoring Data |
| Table 4 | Discharge Estimation of Construction Dewatering |
| Table 5 | Discharge Estimation of Permanent Drainage System |

APPENDICES

| Appendix A | Legal Survey |
|------------|--|
| Appendix B | Proposed Redevelopment Drawings |
| Appendix C | Borehole Logs |
| Appendix D | Certificates of Analysis |
| Appendix E | Single Well Response Test by InSitu Contractors Inc. |

1.0 INTRODUCTION

Pier 27 Toronto (Northeast) Inc. (the Client) intends to redevelop the property located at 25 & 35 Queens Quay East, Toronto, Ontario, M5E 0A4, (hereafter referred to as 'the Site'). MCR was retained to conduct a Geohydrology Assessment for the Site to evaluate the requirement for temporary dewatering and permanent drainage in relation to the proposed redevelopment.

1.1 SCOPE OF WORK

The objectives of the Geohydrology Assessment are to determine the following:

- Hydrogeological conditions of the Site, including the groundwater and phreatic surface, subsurface elevations and flow patterns and the interaction with the design and construction of the proposed development.
- Reviewing the available background information for the Site obtained from MCR's files, City of Toronto, and architectural drawings.
- Estimate the potential temporary dewatering flow rates during construction and assessment of potential impacts on the surrounding environment.
- Estimate the long term flow rates from the Private Water Drainage System (PWDS) of the proposed building.
- Assess the permitting requirements for both dewatering and discharge with the Ministry of Environment, Conservation and Parks (MECP) and the City of Toronto – Toronto Water (the City), respectively.
- Summarize the findings in a Geohydrology Assessment Report.

1.2 SITE DESCRIPTION

The Site is located on the southeast corner of the intersection of Queens Quay East and Yonge Street, in the City of Toronto. The site is rectangular in shape with a total area of approximately 4,400 m².

The Site is bounded by Queens Quay East to the north, Yonge Street to the west and residential developments to the east and south. The ground surface is

relatively flat with a slight slope towards the west. The Site is currently used as an asphalt pave parking lot in the western portion, sales centre in the northeast and construction storage (for Phase II of the development) in the southeast portion.

According to a Survey Plan by KRCMAR presented in Appendix A, the Site is legally described as: Parts of Blocks 18 and 19, Registered Plan 694-E, City of Toronto.

1.3 Proposed Development

The Site is proposed for mixed-use residential/commercial redevelopment with a forty-five [45] storey building with a eleven [11] storey podium (Building F) and a eleven [11] storey building (Building A) plus mechanical penthouse over four [4] levels of below grade parking (Appendix B).

The finished floor elevation (FFE) at ground level is expected to be at an approximate elevation of 77.30 meters above sea level (masl). The P4 level is expected to be at an elevation of 63.24 masl.

Presently, it is assumed that the proposed building structure can be supported on spread/strip footings. The size of the shoring plan layout was assumed to cover approximately 76 m by 58 m.

A sub-floor Private Water Drainage System (PWDS) with perimeter weeping tile will be utilized. A soldier pile and lagging shoring system will be sufficient for the Site except where adjacent structures exist where a caisson wall will be utilized.

1.4 PROPERTY OWNERSHIP

The Site is owned and intended for redevelopment by Pier 27 Toronto (Northeast) Inc. The Client is represented by Ms. Kristine Zwicker with the following contact information:

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, Suite 308

Toronto, Ontario M5E 1A7

Ms. Kristine Zwicker

Email: KZwicker@cityzen.ca

1.5 REVIEW OF PREVIOUS REPORTS

The following geo-environmental reports were provided for review prior to initiating the investigation:

• MCR report titled, *Preliminary Geotechnical Report, Proposed Residential/Commercial Development, Pier 27, Phase 3, Buildings A and F, 25 & 35 Queens Quay East, Toronto, Ontario,* prepared for Pier 27 Toronto (Northeast) Inc., dated February 2021.

2.0 HYDROGEOLOGICAL CONDITIONS

2.1 PHYSICAL SETTING

The Site is located in the eastern area of the City of Toronto and is situated in a mixed-use residential and commercial area. The nearest surface water body is Lake Ontario, located 170 m south of the Site.

The Site is located at an elevation of approximately 76 m above sea level (asl) (250 ft) and the topography across the Site is generally flat. Surrounding area slopes gently down to the southwest.

The Site is bounded by the following properties/features:

North Queens Quay East

South Residential development

Residential development

West Yonge Street

2.2 TOPOGRAPHY

According to the topographic map, published by the Government of Canada; Natural Resources Canada at the Government of Canada website: http://atlas.gc.ca/toporama/en/index.html, the ground surface at the Site is relatively flat with the surrounding area sloping to the southwest, towards Lake Ontario.

2.3 REGIONAL GEOLOGY AND HYDROGEOLOGY

According to the geological map entitled "Quaternary Geology of Ontario, Southern Sheet", published by the Ontario Ministry of Development and Mines, dated 1991, the overburden in the study area consists of predominantly sandy silt to silt matrix, commonly rich in clasts, often high in total matrix carbonate content.

According to the Ontario Ministry of Development and Mines, Map No. 2554 "Bedrock Geology of Ontario, Southern Sheet, 1991", the bedrock typically

consists of Upper Ordovician shale, limestone, dolostone and siltstone. On a regional scale, groundwater generally flows southeast towards Lake Ontario.

2.4 LOCAL GEOLOGY AND HYDROGEOLOGY

On a local scale, geological conditions and hydrogeology are similar to the ones at a regional scale. Locally, near surface groundwater flow may be influenced by underground structures (e.g., service trenches, catch basins, and building foundations or surface watercourses). No surface water features are present onsite and there are no Provincially Significant Wetlands in the vicinity of the Site.

3.0 SCOPE OF INVESTIGATION

3.1 OVERVIEW OF SITE INVESTIGATION

- Twelve boreholes (BH20-1S, BH20-1D, BH20-2 to BH20-4, BH20-5S, BH20-5D, BH20-6S, BH20-6I, BH20-6D and BH20-7 to BH20-8) were drilled by MCR from September 21 to 25, 2020.
- The boreholes were advanced to depths ranging from 3.95 to 14 m.
- Monitoring wells were installed in all borehole except BH20-3, BH20-4 and BH20-7 for long term groundwater monitoring and sampling.
- The boreholes locations are shown in Drawing No. 1 and the records are presented in Appendix C.
- Groundwater levels were recorded from the available monitoring well over various dates and the data is presented in Table 1.
- Groundwater samples were collected from BH20-5S in September 2020 for chemical analysis of the City of Toronto Sewers By-Law criteria.

3.2 MONITORING WELL INSTALLATION

All MCR monitoring wells were installed with a 50 mm diameter schedule 40 PVC pipe and a 3.05m long slotted well screen. Well screens were surrounded by a silica sand pack to at least 0.6 m above the top of screen with a bentonite seal extending from above the sand pack to within 0.5 m of the ground surface. All monitoring wells were completed with a flush mounted cover at ground surface. Monitoring well installation was done in accordance with the *Ontario Water Resources Act*, Sections 35 to 50.

3.3 ELEVATION SURVEYING

The geodetic elevations of the boreholes were surveyed by MCR and referenced to a temporary benchmark established by KRCMAR on September 16, 2020 with a reported elevation of 77.43 masl. All borehole logs are presented in Appendix C and elevations of monitoring wells can be found in Table 1.

3.4 GROUNDWATER SAMPLING

All groundwater sampling activities were conducted in accordance with Ontario Regulation (O.Reg.)153/04, as amended to O.Reg.511/09, July 2011. All monitoring wells were developed prior to sampling activities using a Waterra Hydrolift II (HL-1217) inertial lift pump by purging at least three well volumes or until the monitoring well was purged dry. Groundwater samples were obtained at least 24 hours' post-development under static conditions. No samples were field filtered prior to laboratory analysis, in accordance with the standard.

3.5 GROUNDWATER ANALYSIS

All groundwater samples were submitted to ALS Laboratory Group (ALS) of Richmond Hill, Ontario, certified by the Canadian Association for Laboratory Accreditation (CALA), for chemical analysis. The Certificates of Analysis received are included in Appendix D. The contact information for the laboratory used is included below.

ALS Laboratory Group

95 West Beaver Creek Road Richmond Hill, ON L4B 1H2

All groundwater samples were submitted for bulk chemical analysis for the criteria provided in the *Toronto Municipal Code, Chapter 681, Sewers By-law.* The results of chemical analysis were compared to the criteria provided in *Table 1 – Limits for Sanitary and Combined Sewers Discharge and Table 2 – Limits for Storm Sewer Discharge.* These guidelines establish the maximum allowable concentrations of specific analytical parameters for water discharged into either the municipal sanitary and/or storm sewer system respectively.

4.0 INVESTIGATION RESULTS

4.1 GEOLOGY

The borehole elevations ranged from 76.08 masl (BH 20-2) to 77.06 masl (BH 20-6). Based on the investigation by the geologic formations beneath the Site are illustrated in borehole logs (Appendix C) and include the following (from surface to depth):

Pavement: An asphalt layer, 75 mm in thickness, was observed at the surface of boreholes 20-4, 20-5D and 20-7. A 75 mm thick concrete layer was present at the surface of borehole 20-8. Granular fill, varying from 425 to 525 mm in thickness, underlies the asphalt/concrete in the boreholes.

Fill: Loose to compact fill consisting of sand, silt, gravel and clay/clayey silt was present at the surface of boreholes 20-1D, 20-2, 20-3 and 20-6D and below the pavement at boreholes 20-4, 20-5D, 20-7 and 20-8. The moist to wet fill contained trace clay, sand, gravel and clinker, trace to some organics, and debris such as decayed wood and brick fragments.

For the purpose of offsite disposal, the type/quantity and extent of existing fill/organic materials/granular fill layers should be explored by further test pit investigation, prior to contract award.

Sand: A layer of very loose to loose, medium to fine sand was detected below the fill at boreholes 20-1D and 20-8 and extended to depths of 6.10 and 5.20 m, respectively. The dark brown to black sand contained some silt and trace gravel and was in a wet condition.

Silt/Silty Clay/Sandy Silt: A layer of soft to hard silt/silty clay/sandy silt was encountered below fill/sand at all boreholes except 20-1S, 20-5S, 20-6S and 20-8. The deposit was in a moist to wet condition and contained traces to some sand, trace gravel, shells, clay and organics. The dark brown to black and black to grey silt/silty clay silt extended to depths ranging from 5.20 to 12.50 m.

Although no cobbles or boulders were encountered during the

geotechnical investigation, using 100 to 150 mm boreholes, the proposed excavations will be in soils that went through historic periods of glaciation. As a result, glacial drop stones, ranging from gravel to boulders can be encountered within the overburden.

Shale Bedrock: Grey moist shale was found below the silty clay at boreholes 20-1D, 20-5D and 20-6D at depths ranging from 11.90 to 13.40 m and extended to the maximum depth of all boreholes, at elevations ranging from 63 to 64.4 m.

Groundwater: Upon completion of drilling all the boreholes remained dry.

On September 28, 2020, groundwater levels were measured at depths ranging from 2.25 to 11.29 m in all monitoring wells.

On October 1, 2020, groundwater levels were measured at depths ranging from 2.28 to 11.40 m in all monitoring wells. On October 5, 2020, groundwater levels were measured at depths ranging from 2.26 to 11.26 m in all monitoring wells. On October 9, 2020, groundwater levels were measured at depths ranging from 2.26 to 11.55 m in all monitoring wells.

On October 14, 2020, groundwater levels were measured at depths ranging from 2.25 to 11.20 m in all monitoring wells. On October 19, 2020, groundwater levels were measured at depths ranging from 2.27 to 11.64 m in all monitoring wells. The results are summarized on the Record of Borehole Sheets in Appendix C and Table 1.

4.2 GROUNDWATER LEVEL MONITORING

All current and past groundwater monitoring data is presented in Table 1. It should be noted that groundwater levels are subject to seasonal fluctuations. All groundwater levels were measured manually using an electric water level meter and with respect to the geodetic borehole elevations within the property boundary. The monitoring wells must be decommissioned, prior to construction, in accordance with Regulation 903 by a qualified contractor.

The interpreted groundwater flow direction is based on the 2020 rounds of water

table elevation measurements. The groundwater levels were monitored from September to October 2020 as part of the six rounds of water level readings. The interpreted local direction of hydraulic movement across the Site is inferred to be in a southern direction, towards Lake Ontario.

4.3 GROUNDWATER QUALITY

The groundwater sample collected from BH20-5S in September 2020 was analyzed for the City of Toronto Sewers By-Law criteria. The results of chemical analysis (Table 2) indicate that the sample complies with the *Table 1 Limits for Sanitary & Combined Sewers Discharge* for all parameters analyzed. The following exceedances were recorded for the *Table 2 Limits for Storm Sewer Discharge*: Total Cyanide (0.17 mg/L vs. 0.02 mg/L), Total Manganese (0.208 mg/L vs. 0.05 mg/L) and Total Zinc (0.065 mg/L vs. 0.04 mg/L).

4.4 GROUNDWATER DISCHARGE ASSESSMENT

Presently, the groundwater onsite can be discharged to the City sanitary or combined sewer system with no additional filtration or treatment. A filtration/treatment system cyanide, manganese and zinc would be required prior to discharging to the storm sewer system. A dewatering contractor should be approached to explore the possibility of treatment if discharge to the storm sewer is required.

5.0 REVIEW AND EVALUATION

5.1 TEMPORARY DEWATERING ASSESSMENT

The excavation for the proposed four level underground parking structure will extend into shale bedrock. Positive dewatering such as well points will be required for the proposed excavation above shale. Onsite soils might be subject to localized piping during dewatering. Creation of piping channels may result in a substantial increase in the volume of both temporary dewatering and permanent drainage.

In addition, the (weathered) sedimentary bedrock can be fractured, fissured, or contain water-bearing bedding planes. When these bedding planes are intercepted in rock excavation, a substantial amount of water, often under significant hydrostatic head, may be encountered. The depths and condition of shale bedrock vary across the Site; therefore, its quality should be confirmed during shoring installation and general excavation through inspections in the field.

For the proposed four underground levels, groundwater is required to be drawn down a minimum of 1 m below the underside of the footing. However, for the purpose of temporary/construction dewatering, given the encountered subsurface conditions, groundwater cannot be lowered with well points below the average top elevation of shale bedrock at approximately 64.40 masl.

Localized trenches and sumps can be used within bedrock to lower the water level below the underside of the P4 slab and footings. The assumed foundation elevation is approximately 61.75 masl. Therefore, groundwater will need to be lowered to an elevation of 60.75 masl. This result is preliminary and should be confirmed during the construction phase and final stage of detailed shoring.

The average ground water level recorded in the monitoring wells is taken as the September 2020 readings at an elevation of 72.11 masl (Table 3), representing an approximate 11.35 m hydrostatic head requiring dewatering. The size of the shoring plan layout was assumed to cover approximately 76 m by 58 m.

Theoretically, the groundwater drawdown for a single well pumping can be described as:

$$Q = -2\pi r K h \frac{dh}{dr} \tag{1}$$

And further we have:

$$h^{2} = -\frac{Q}{\pi K} \ln(r/r_{w}) + h_{w}^{2}$$
 (2)

Where:


h [m] is the height of the water table above an impervious base

Q [m³/day]is the rate of pumping discharge

K [m/day] is hydraulic conductivity

R [m] is the radius from the centre of well location

 $r_w[m]$ is the radius of pumping well (see Schematic A below).



Schematic A: Radial flow to an unconfined aquifer (Todd 1980)

5.1.1 Numerical Analysis

The abovementioned Site parameters were used to calculate the estimated steady state discharge rate for temporary construction dewatering. Groundwater monitoring data is presented in Table 3. The calculations for temporary dewatering rates are shown in Table 4.

From the observed soil types and based on soil sample descriptions (*Todd*, 1980; Mays, 2001; and Craig, 2004) and the Single Well Response Test by InSitu Contractors Inc. (Appendix E), the average hydraulic conductivity (K) of the aquifer was conservatively estimated at 0.3 m/day. The estimated steady state discharge rate for temporary construction dewatering was calculated at 249 m³/day (46 USG/min), with a safety factor of 1.50.

The initial drawdown pumping rate would be higher to relieve the stored groundwater pressure (prior to the start of construction). Considering the soils onsite being mainly a mixture of sandy silt/silty clay and shale, the average specific yield is estimated as 3%. The total yield from the groundwater stored within the soil pore would be about 1,505 m³.

The additional discharge rate to remove the groundwater store in the pore spaces during initial drawdown could range form 38 m³/day for a 40-day drawdown period to 50 m³/day for a 30-day drawdown period. A factor of two should be applied to account for unforeseen conditions, including potential impact of wet weather conditions and fluctuations in the groundwater table.

Additional pumping may be required to remove surface water from the Site. Assuming a rainfall event of 25 mm over a 24 hour period, about 110 m³/day of water may need to be removed from the Site following rain events.

Accordingly, the following pumping rates are required:

| | Typical | Maximum | Units |
|---------------|---------|---------|--------|
| Groundwater | 249 | 349 | m³/day |
| Precipitation | 0 | 110 | m³/day |
| Total | 249 | 459 | m³/day |

5.2 PERMANENT FOUNDATION DRAIN FLOW RATES

For the proposed redevelopment, the ground finished floor elevation (FFE) is expected to be at an Elevation of 77.30 meters above sea level (masl). The P4 FFE will be at an approximate elevation of 63.24 masl. A sub-floor Private Water Drainage System (PWDS) with perimeter/underfloor weeping tile is proposed. The invert of the PWDS is assumed to be at an approximate elevation of 62.75 masl.

The proposed PWDS is shown on Drawing No. 2. The slotted pipes should slope to a sump at a minimum 1% slope. Perimeter drainage pipes, with a positive gravity outlet, should be solid PVC with a minimum of 0.5% slope. In addition, silt traps must be provided at convenient/accessible locations.

5.2.1 Numerical Analysis

The abovementioned Site parameters were used to calculate the estimated steady state discharge rate for the PWDS. Groundwater monitoring data is presented in Table 3. The calculations for permanent drainage flow rates are shown in Table 5.

From the observed soil types and based on soil sample descriptions (*Todd*, 1980; Mays, 2001; and Craig, 2004) and the Single Well Response Test by InSitu Contractors Inc, the average hydraulic conductivity (K) of the aquifer was estimated at 0.05 m/day due to the presence of shale bedrock.

The estimated steady state discharge rate/average daily flow rate for the PWDS was calculated at approximately 31 m³/day (6 USG/min) with a safety factor of 1.0. The peak flow rate was calculated to be 46 m³/day (8 USG/min) by applying a safety factor of 1.50.

Please note that due to the presence of bedding planes/vertical fissures in the bedrock, the discharge volume might increase with time. Monitoring of permanent sumps is recommended for quality and quantity of discharge.

5.3 MECP PERMIT TO TAKE WATER REQUIREMENT

The Permit to Take Water (PTTW) requirements for construction site dewatering have been updated to the current O.Reg.63/16 amendment to Environmental Protection Act. In accordance with the updated regulation, construction site dewatering will require a complete PTTW application when water takings greater than 400,000 L/day are predicted. Groundwater taking between 50,000 L/day and 400,000 L/day will require a limited PTTW via an online application process through the Environmental Activity and Sector Registry (EASR). Groundwater taking from a proposed building structure by means of a PWDS will require a PTTW when water taking is greater than 50,000 L/day. The complete permit application process for PTTW takes approximately twelve weeks to review and is required prior to applying for the discharge permits.

The maximum anticipated temporary dewatering discharge rate was calculated at approximately 459 m³/day. Therefore, a complete PTTW application will be required to be applied for with the MECP.

The maximum/peak flow rate from the PWDS was calculated at approximately 46 m³/day. Therefore, a PTTW application for the PWDS will not be required for the proposed building.

In accordance with the current Ontario Regulation 387/04 for Water Taking, every person to whom a permit has been issued under Section 34 of the Act shall collect and record data on the volume of water taken daily. The data collected shall be measured by a flow meter or calculated using a method acceptable to a Director.

5.4 TORONTO WATER DISCHARGE PERMIT REQUIREMENTS

The City of Toronto – Toronto Water requires that any private water to be discharged into the City sewer system must have a permit or agreement in place in order to discharge; this applies to all water not purchased from the City water supply. For temporary dewatering during the construction phase, this includes all groundwater and storm water that is collected or encountered during site excavation. For the PWDS, this includes all groundwater that is constantly

pumped as a result of the PWDS elevation located below the groundwater table elevation or through storm water infiltration.

The groundwater quality sample collected in September 2020 indicates that the water onsite could be discharged into the City sanitary and combined sewer system without additional filtration/treatment required. A filtration and treatment system for cyanide, manganese and zinc would be required prior to discharging into the storm sewer system. A short-term temporary discharge permit must be applied for construction dewatering with Toronto Water.

A long-term permanent discharge permit must be applied for the proposed PWDS since the drainage system is located below the long-term groundwater elevation. The permanent discharge permit will involve coordination with the mechanical and site servicing consultant to provide calculations and drawing specifications for the ultimate discharge location and the sampling port required by Toronto Water.

5.5 ENVIRONMENTAL PROTECTION

The Site is located within the Lake Ontario drainage basin and the Lake is approximately 170 m south of the Site. There are no ecological features, areas of natural significance, or provincially significant wetlands in the vicinity of the Site. The Site is located in the City of Toronto urban environment, which obtains its municipal water supply from Lake Ontario. Therefore, there are no potable groundwater users within the vicinity of the Site.

The proposed redevelopment plan will remove all the overburden to a depth of approximately 15 to 16 mbgs, from the interior Site area. Temporary groundwater dewatering will lower the groundwater table to below the underground parking foundation levels. The extracted water will be discharged into the sanitary sewer or, with some filtration or treatment, into the storm sewer. Updatedgroundwater monitoring will be conducted by the dewatering contractor prior to and during construction activities to ensure that no additional adverse groundwater impacts are identified throughout the project's construction.

6.0 CONCLUSIONS AND RECOMMENDATIONS

McClymont&Rak Engineers Inc. was retained to conduct a Geohydrology Assessment for the Site in relation to the proposed redevelopment. The Site is currently used as an asphalt pave parking lot in the western portion, sales centre in the northeast and construction storage (for Phase II of the development) in the southeast portion.

The Site is proposed for mixed-use residential/commercial redevelopment with a forty-five [45] storey building with a eleven [11] storey podium (Building F) and a eleven [11] storey building (Building A) plus mechanical penthouse over four [4] levels of below grade parking (Appendix B).

The finished floor elevation (FFE) at ground level is expected to be at an approximate elevation of 77.30 meters above sea level (masl). The P4 level is expected to be at an elevation of 63.24 masl.

Presently, it is assumed that the proposed building structure can be supported on spread/strip footings. The size of the shoring plan layout was assumed to cover approximately 76 m by 58 m.

A sub-floor Private Water Drainage System (PWDS) with perimeter weeping tile will be utilized. A soldier pile and lagging shoring system will be sufficient for the Site except where adjacent structures exist where a caisson wall will be utilized.

The excavation for the proposed four level underground parking structure will extend into shale bedrock. Positive dewatering such as well points will be required for the proposed excavation above shale. Onsite soils might be subject to localized piping during dewatering. Creation of piping channels may result in a substantial increase in the volume of both temporary dewatering and permanent drainage.

In addition, the (weathered) sedimentary bedrock can be fractured, fissured, or contain water-bearing bedding planes. When these bedding planes are intercepted in rock excavation, a substantial amount of water, often under significant hydrostatic head, may be encountered. The depths and condition of shale bedrock vary across the Site; therefore, its quality should be confirmed during shoring installation and

general excavation through inspections in the field.

For the proposed four underground levels, groundwater is required to be drawn down a minimum of 1 m below the underside of the footing. However, for the purpose of temporary/construction dewatering, given the encountered subsurface conditions, groundwater cannot be lowered with well points below the average top elevation of shale bedrock at approximately 64.40 masl.

Localized trenches and sumps can be used within bedrock to lower the water level below the underside of the P4 slab and footings. The assumed foundation elevation is approximately 61.75 masl. Therefore, groundwater will need to be lowered to an elevation of 60.75 masl. This result is preliminary and should be confirmed during the construction phase and final stage of detailed shoring.

The average ground water level recorded in the monitoring wells is taken as the September 2020 readings at an elevation of 72.11 masl (Table 3), representing an approximate 11.35 m hydrostatic head requiring dewatering.

The anticipated temporary construction dewatering was calculated between 249 – 459 m³/day (46 – 84 USG/min). Therefore, based on the amended O.Reg. 63/16 to the Environmental Protection Act, a complete PTTW application will be required from the MECP and a temporary discharge permit will be required from the Toronto Water.

The maximum/peak discharge rate for the PWDS was calculated at approximately 46 m³/day (8 USG/min). Therefore, a PTTW will not be required from the MECP for the PWDS. A long-term permanent discharge permit will be required from Toronto Water since the drainage will be installed below the long-term groundwater elevation.

The selected dewatering contract must be performance driven and the contractor must provide a performance bond. In addition, upon completion of system's installation, the contractor must produce a written statement that "The system installed is robust enough to lower and maintain groundwater at least 1.0 m below the lowest footing elevation, without impacting the integrity of shoring or foundation soils."

Presently, the groundwater onsite can be discharged to the City sanitary or combined sewer system with no additional filtration or treatment. A filtration and treatment system for cyanide, manganese and zinc would be required prior to discharging to the storm sewer system. A dewatering contractor should be approached to explore the possibility of treatment if discharge to the storm sewer is required.

The application process, where a PTTW is required, can take at least three months for a review by the MECP and is required to be approved prior to applying for discharge permits. It is recommended that applications to Toronto Water for discharge permits be applied for at least three months prior to the required start dates. Applications are to be supported by drawings and calculations provided by the mechanical and the site servicing consultant and coordination is required amongst all disciplines. The information provided in this report can be relied upon by Toronto Water – Environmental Monitoring & Protection Unit (TW-EM&P) regarding the short and long term Sanitary Discharge Agreement applications for the Site.

7.0 REFERENCES

- 1. Ontario Ministry of the Environment. Soil, Ground Water and Sediment Standards for Use Under Part XV.1 of the Environmental Protection Act. April15, 2011.
- 2. Ministry of Northern Development and Mines. *Quaternary Geology of Toronto and Southern Ontario Southern, Sheet Map 2504*, 1980.
- 3. Ministry of Northern Development and Mines. *Bedrock Geology of Ontario-Southern Sheet*, 1991.
- 4. D.K. Todd, *Groundwater Hydrology*, 2nd Edition, John Wiley & Sons, New York, 1980.
- 5. L.W. Mays, *Water Resources Engineering*, 1st Edition, John Wiley & Sons, New York, 2001.
- 6. MCR report titled, *Preliminary Geotechnical Report, Proposed Residential/Commercial Development, Pier 27, Phase 3, Buildings A and F, 25 & 35 Queens Quay East, Toronto, Ontario, prepared for Pier 27 Toronto (Northeast) Inc., dated November 2020.*

8.0 STATEMENT OF LIMITATIONS

McClymont&Rak Engineers, Inc. (MCR) conducted the work associated with this report in accordance with the scope of services, time and budget limitations imposed for this work. The work has been conducted according to reasonable and generally accepted local standards for an environmental consultant at the time of the work. No other warranty or representation, expressed or implied, is included or intended in this report.

The work was designed to provide an overall assessment of the environmental conditions at the Site. The conclusions presented in this report are based on the information obtained during the investigation. The work is intended to reduce the client's risk with respect to environmental impairment. No work can completely eliminate the possibility of further environmental impairment on the Site.

It should be noted that subsurface conditions might vary at locations and depths other than those locations where borings, surveys or explorations were made by MCR. Other contaminants, not tested for in this work, may also potentially be present on the Site. Even with exhaustive investigation, it is not possible to warranty the Site will be free of contaminants. Should conditions, not observed during the work, become apparent, MCR should be immediately notified to assess the situation and conduct additional work, where required. The findings of this report are based on conditions as they were observed at the time of the work.

No assurance is made regarding changes in conditions subsequent to the time of the work. Remediation cost estimates is based on the available information. The estimated costs for remediation only represent the costs for the clean-up of known contaminants that have been identified during the work. Additional costs may be incurred as a result of other contaminants or areas of contamination identified by subsequent work.

Regulatory statutes are subject to interpretation. These statutes and their interpretation may change over time, thus these issues should be reviewed with appropriate legal counsel.

MCR relied on information provided by others in this report. MCR cannot guarantee the accuracy, completeness and reliability of the information provided by others, although MCR staff attempted to seek clarification on information provided and verifies authenticity, where practical.

The report and its attachments were prepared for and made available for the sole use of the client. MCR will not be responsible for any use or interpretation of the information contained in this report by any other party without the prior expressed written consent of MCR.

9.0 CLOSURE

In accordance with your request and authorization, McClymont and Rak Engineers Inc. completed this Geohydrology Assessment Report. This report presented the methodology, findings and conclusions of the investigation. The Statement of Limitations for all work performed as part of this investigation is included.

We trust that the information provided in this report is sufficient for your present requirements. Should you have any further questions, please do not hesitate to contact our office. Thank you for retaining McClymont&Rak Engineers, Inc. for this project.

Respectfully,

McClymont&Rak Engineers Inc.

Prepared By:

Richard Sukhu, B.Eng.





Reviewed By:

Lad Rak, P.Eng., M.Eng., QP_{ESA}

Date of Issue: March 1, 2021

| FIG | U | R | ES |
|------------|---|---|-----------|
|------------|---|---|-----------|







NTS

.

2

TABLES

McCLYMONT AND RAK ENGINEERS INC. **GEO-ENVIRONMENTAL CONSULTANTS**

TABLE 1 CONSTRUCTION DETAILS AND ELEVATION OF MONITORING WELLS

| MONITORING WELL ID | GROUND SURFACE ELEVATION | WATER LEVEL | GROUNDWATER ELEVATION | DATE OF MEASUREMENT | DEPTH OF WELL | DEPTH OF BENTONITE | LENGTH OF SCREEN | INSIDE DIAMETER OF PIPE | TOP OF MONITORING WELL |
|-----------------------|--------------------------------|---------------|--------------------------|------------------------|------------------|-----------------------|---------------------|-------------------------------|------------------------------|
| | (masl) | (mbgs) | (masl) | (mm/dd/yyyy) | (mbgs) | (mbgs) | (m) | (mm) | WELL |
| | | 2.55 | 74.38 | 9/28/2020 | | | | | |
| | | 2.58 | 74.35 | 10/1/2020 | | | | | |
| BH 20-1S | 76.93 | 2.61 | 74.32 | 10/5/2020 | 3.96 | 0.30 | 3.05 | 50 | FLUSH MOUNT |
| BI1 20-10 | 70.50 | 2.62 | 74.31 | 10/9/2020 | 0.50 | 0.00 | 0.00 | 30 | 1 LOOIT WOON |
| | | 2.59 | 74.34 | 10/14/2020 | | | | | |
| | | 2.64 | 74.29 | 10/19/2020 | | | | | |
| | | 7.46 | 69.47 | 9/28/2020 | | | | | |
| | | 7.50 | 69.43 | 10/1/2020 | | | | | |
| DI I 00 4D | 70.00 | 7.54 | 69.39 | 10/5/2020 | 40.40 | 0.75 | 2.05 | 50 | FLUCLIMOUN |
| BH 20-1D | 76.93 | 7.56 | 69.37 | 10/9/2020 | 12.19 | 9.75 | 3.05 | 50 | FLUSH MOUN |
| | | 7.50 | 69.43 | 10/14/2020 | | | | | |
| | | 7.50 | 69.43 | 10/19/2020 | | | | | |
| | | 2.71 | 74.27 | 9/28/2020 | | | | | |
| | | 2.69 | 74.29 | 10/1/2020 | | | | | |
| | | 2.72 | 74.26 | 10/5/2020 | | | | | |
| BH 20-2 | 76.98 | 2.72 | 74.26 | 10/9/2020 | 5.47 | 1.01 | 3.05 | 50 | FLUSH MOUN |
| | | 2.70 | 74.28 | 10/14/2020 | | | | | |
| | | 2.78 | 74.20 | 10/19/2020 | | | | | |
| | | 2.55 | 74.48 | 9/28/2020 | | | | | |
| | | 2.56 | 74.47 | 10/1/2020 | | | | | |
| | | 2.55 | 74.48 | 10/5/2020 | | 0.60 | 3.05 | | FLUSH MOUNT |
| BH 20-5S | 77.03 | 2.57 | 74.46 | 10/9/2020 | 4.27 | | | 50 | |
| | | | | 10/9/2020 | | | | | |
| | | 2.58 | 74.45 | | | | | | |
| | | 2.56 | 74.47 | 10/19/2020 | | | | | |
| BH 20-5D | | 11.29 | 65.74 | 9/28/2020 | | | | | |
| | 77.03 | 11.40 | 65.63 | 10/1/2020 | 13.41 | 9.45 | 3.05 | 50 | FLUSH MOUNT |
| | | 11.26 | 65.77 | 10/5/2020 | | | | | |
| | | 11.55 | 65.48 | 10/9/2020 | | | | | |
| | | 11.20 | 65.83 | 10/14/2020 | | | | | |
| | | 11.64 | 65.39 | 10/19/2020 | | | | | |
| | | 2.66 | 74.40 | 9/28/2020 | | | | | |
| | | 2.66 | 74.40 | 10/1/2020 | | | | | |
| BH 20-6S | 77.06 | 3.36 | 73.70 | 10/5/2020 | 4.57 | 0.60 | 3.05 | 50 | FLUSH MOUN |
| B1120 00 | 77.00 | 2.73 | 74.33 | 10/9/2020 | 1.07 | 0.00 | 0.60 3.05 | 00 | 1 20011 110011 |
| | | 2.69 | 74.37 | 10/14/2020 | | | | | |
| | | 2.69 | 74.37 | 10/19/2020 | | | | | |
| | | 2.84 | 74.22 | 9/28/2020 | | | | | |
| | | 2.89 | 74.17 | 10/1/2020 | | | | | |
| BH 20-6I | 77.06 | 2.90 | 74.16 | 10/5/2020 | 9.14 | 5.40 | 5.49 3.05 | 50 | FLUSH MOUN |
| טוו בט-טו | 11.00 | 2.90 | 74.16 | 10/9/2020 | 9.14 | 5.49 | | | FLUSH WUUN |
| | | 2.82 | 74.24 | 10/14/2020 | | | | | 1 |
| | | 2.83 | 74.23 | 10/19/2020 | | | | | |
| | | 9.80 | 67.26 | 9/28/2020 | | | | | |
| | | 9.82 | 67.24 | 10/1/2020 | 1 | | | | |
| | | 10.00 | 67.06 | 10/5/2020 | | _ | | | |
| BH 20-6D | 77.06 | 9.83 | 67.23 | 10/9/2020 | 12.19 | 9.75 | 3.05 | 50 | FLUSH MOUN |
| | | 9.80 | 67.26 | 10/14/2020 | | | | | |
| | | 9.84 | 67.22 | 10/19/2020 | | | | | |
| | | 2.25 | 74.80 | 9/28/2020 | | | | | |
| | | 2.28 | 74.77 | 10/1/2020 | | | | | |
| | 77.05 | 2.26 | 74.77 | 10/5/2020 | | | | | |
| BH 20-8 | | 2.26 | 74.79 | 10/5/2020 | 4.57 | 0.91 | 3.05 | 50 | FLUSH MOUN |
| | | | | | | | | | |
| | | 2.25 | 74.80 | 10/14/2020 | | | | | |
| | | 2.27 | 74.78 | 10/19/2020 | 0.00 | | 1 | | |
| | 70.00 | | | | | | | | |
| Min Max | 76.93 77.06 | 2.25 11.64 | 65.39 74.80 | - | 3.96 13.41 | - | - | - | - |

NOTE:

mbgs - meters below ground surface masl - meters above sea level

N/A - Not Applicable

NF - Not Found

McCLYMONT AND RAK ENGINEERS INC. GEO-ENVIRONMENTAL CONSULTANTS

TABLE 2
GROUNDWATER ANALYTICAL RESULTS - CITY OF TORONTO SEWERS BY-LAW DISCHARGE CRITERIA MCR JOB#: GE4842

SITE ADDRESS: 15 Queens Quay East, Toronto, ON

| PARAMETER | UNITS | LIMITS FOR STORM | LIMITS FOR SANITARY & COMBINED SEWERS | BH20-5S | |
|--|-----------|------------------|--|-----------|--|
| | | SEWER DISCHARGE | DISCHARGE | 30-Sep-20 | |
| pH | pH Units | 6.0 - 9.5 | 6.0 - 11.5 | 8.01 | |
| Total Suspended Solids | mg/L | 15 | 350 | 7.6 | |
| Fluoride (F-) | mg/L | - | 10 | 0.73 | |
| Total Kjeldahl Nitrogen (TKN) | mg/L | - | 100 | 8.57 | |
| Total Phosphorus (P) | mg/L | 0.4 | 10 | 0.1220 | |
| Total Cyanide (CN) | mg/L | 0.02 | 2 | 0.17 | |
| Escherichia Coli | CFU/100mL | 200 | - | 1 | |
| Total Aluminum (AI) | mg/L | - | 50 | 2.09 | |
| Total Antimony (Sb) | mg/L | - | 5 | 0.0019 | |
| Total Arsenic (As) | mg/L | 0.02 | 1 | 0.0091 | |
| Total Cadmium (Cd) | mg/L | 0.008 | 0.7 | 0.000067 | |
| Total Chromium (Cr) | mg/L | 0.08 | 4 | <0.0050 | |
| Total Cobalt (Co) | mg/L | - | 5 | 0.0023 | |
| Total Copper (Cu) | mg/L | 0.04 | 2 | 0.0055 | |
| Total Lead (Pb) | mg/L | 0.12 | 1 | 0.0231 | |
| Total Manganese (Mn) | mg/L | 0.05 | 5 | 0.208 | |
| Total Manganese (Min) Total Mercury (Hg) | | 0.0004 | 0.01 | 0.0000227 | |
| Total Molybdenum (Mo) | mg/L | | 5 | 0.0000227 | |
| • ' | mg/L | 0.08 | 2 | 0.0063 | |
| Total Scienium (Sc) | mg/L | 0.08 | 1 | <0.00050 | |
| Total Selenium (Se) | mg/L | | 5 | <0.00050 | |
| Total Silver (Ag) | mg/L | 0.12 | | | |
| Total Tin (Sn) | mg/L | - | 5 | 0.0011 | |
| Total Titanium (Ti) | mg/L | - | 5 | 0.0772 | |
| Total Zinc (Zn) | mg/L | 0.04 | 2 | 0.065 | |
| Chromium (VI) | mg/L | 0.04 | 2 | <0.00050 | |
| Biological Oxygen Demand | mg/L | 15 | 300 | <3.0 | |
| Total Oil & Grease (Animal/Vegetable) | mg/L | - | 150 | <5.0 | |
| Total Oil & Grease Mineral/Synthetic | mg/L | - | 15 | <2.5 | |
| Phenols-4AAP | mg/L | 0.008 | 1 | <0.0010 | |
| Benzene | μg/L | 2 | 10 | <0.50 | |
| Chloroform | μg/L | 2 | 40 | <1.0 | |
| 1,2-Dichlorobenzene | μg/L | 5.6 | 50 | <0.50 | |
| 1,4-Dichlorobenzene | μg/L | 6.8 | 80 | <0.50 | |
| cis-1,2-Dichloroethylene | μg/L | 5.6 | 4000 | <0.50 | |
| Dichloromethane (Methylene Chloride) | μg/L | 5.2 | 2000 | <2.0 | |
| trans-1,3-Dichloropropene | μg/L | 5.6 | 140 | <0.50 | |
| Ethylbenzene | μg/L | 2 | 160 | <0.50 | |
| 1,1,2,2-Tetrachloroethane | μg/L | 17 | 1400 | <0.50 | |
| Tetrachloroethylene | μg/L | 4.4 | 1000 | <0.50 | |
| Toluene | μg/L | 2 | 16 | <0.50 | |
| Trichloroethylene | μg/L | 7.6 | 400 | <0.50 | |
| o-Xylene | μg/L | - | - | <0.50 | |
| m+p-Xylenes | μg/L | - | - | <1.0 | |
| Xylene (Total) | μg/L | 4.4 | 1400 | <1.1 | |
| Total PAHs (18 PAHs) | μg/L | 2 | 5 | <1.7 | |
| Bis(2-ethylhexyl)phthalate | μg/L | 8.8 | 12 | <2.0 | |
| 3,3'-Dichlorobenzidine | μg/L | 0.8 | 2 | <0.40 | |
| Di-n-butylphthalate | μg/L | 15 | 80 | <1.0 | |
| Pentachlorophenol | μg/L | 2 | 5 | <1.0 | |
| Total PCBs | μg/L | 0.4 | 1 | <0.040 | |
| Nonylphenol | μg/L | 1 | 20 | <1.0 | |
| Total Nonylphenol Ethoxylates | μg/L | 10 | 200 | <2.0 | |


| BOLD | Exceeds Criteria - Table 1 Sanitary and Combined Sewer |
|------|---|
| BOLD | Non-Detect Exceeds Criteria - Table 1 Sanitary and Combined Sewer |
| BOLD | Exceeds Criteria - Table 2 Storm Sewer Criteria |
| BOLD | Non-Detect Exceeds Criteria - Table 2 Storm Sewer Criteria |

Project: Proposed Residential Development Location: 15 Queens Quay East, Toronto, ON

Date: September-20 Project #: MG4842

TABLE 3
GROUNDWATER MONITORING DATA

| Borehole Number | Surface Elevation | Water Level Depth Elevation | | Monitoring Date | |
|--------------------|----------------------|-----------------------------|--------|-----------------|-------|
| | (masl) | (mbgs) | (masl) | (mm/dd/yyy) | NOTES |
| | | | | | |
| BH 20-1S | 76.93 | 2.55 | 74.38 | 9/28/2020 | |
| BH 20-1D | 76.93 | 7.46 | 69.47 | 9/28/2020 | |
| BH 20-2 | 76.98 | 2.71 | 74.27 | 9/28/2020 | |
| BH 20-5S | 77.03 | 2.55 | 74.48 | 9/28/2020 | |
| BH 20-5D | 77.03 | 11.29 | 65.74 | 9/28/2020 | |
| BH 20-6S | 77.06 | 2.66 | 74.40 | 9/28/2020 | |
| BH 20-6I | 77.06 | 2.84 | 74.22 | 9/28/2020 | |
| BH 20-6D | 77.06 | 9.80 | 67.26 | 9/28/2020 | |
| BH 20-8 | 77.05 | 2.25 | 74.80 | 9/28/2020 | |
| | | | | | |
| Average | 77.01 | 4.90 | 72.11 | | |
| Max | | | 74.80 | | |





MCR McCLYMONT & RAK ENGINEERS, INC. GEO-ENVIRONMENTAL CONSULTANTS

GROUNDWATER

Project: **Proposed Residential Development** Location: 15 Queens Quay East, Toronto, ON

Date: September-20 Project #: MG4842

TABLE 4 DISCHARGE ESTIMATION OF CONSTRUCTION DEWATERING

| Site Parameters | Units |
|---|--------------|
| Initial Water Level before Dewatering | 72.11 (m) |
| Lowest Water Level during Construction Dewatering | 60.75 (m) |
| Length of Site X | 76.00 (m) |
| Width of Site W | 58.00 (m) |
| Equivalent Radius r _e | 37.46 (m) |
| Hydraulic Conductivity of Aquifer (k) | 0.30 (m/day) |
| Aquifer Bottom Elevation | 58.75 (m) |
| Applied Radius of Influence (Ro) | 63.52 (m) |
| Height btw Initial Water Level and Aquifer Bottom (H) | 13.36 (m) |
| Height btw Lowest Water Level and Aquifer Bottom (hw) | 2.00 (m) |
| Radius of Influence (R) | 100.98 (m) |
| Factor of Safety (FS) | 1.50 |

$$Q = \frac{\pi k (H^2 - h_w^2)}{Ln(R/r)}$$



MCR McCLYMONT & RAK ENGINEERS, INC. GEO-ENVIRONMENTAL CONSULTANTS

GROUNDWATER

Project: **Proposed Residential Development** Location: 15 Queens Quay East, Toronto, ON


Date: September-20 Project #: MG4842


TABLE 5 DISCHARGE ESTIMATION OF PERMANENT DRAINAGE SYSTEM

| Site Parameters | Units |
|---|--------------|
| Initial Water Level before Dewatering | 72.11 (m) |
| Lowest Water Level under PDS conditions | 62.75 (m) |
| Length of Site X | 76.00 (m) |
| Width of Site W | 58.00 (m) |
| Equivalent Radius r _e | 37.46 (m) |
| Hydraulic Conductivity of Aquifer (k) | 0.05 (m/day) |
| Aquifer Bottom Elevation | 62.75 (m) |
| Applied Radius of Influence (Ro) | 21.37 (m) |
| Height btw Initial Water Level and Aquifer Bottom (H) | 9.36 (m) |
| Height btw Lowest Water Level and Aquifer Bottom (hw) | 0.00 (m) |
| Radius of Influence (R) | 58.83 (m) |
| Factor of Safety (FS) | 1.00 |

$$Q = \frac{\pi k (H^2 - h_w^2)}{Ln(R/r)}$$

| Estimated steady-state discharge of dewatering | 30.51 (m³/day) | 6 (USG/min) |
|--|-----------------------------|-------------|
| Estimated peak discharge of dewatering | 45.77 (m ³ /day) | 8 (USG/min) |





Survey


Project No.

1:350

2020-09-15



QUEENS QUAY E



 Copyright of this drawing is reserved by the Architect. The drawing and all associated documents are an instrument of service by the Architect. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Architect.

2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application, the Architect will provide written/graphic clarification or supplementary information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.

3. Drawings are not to be scaled for construction. The Contractor is to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the Architect before commencing any work.

4. Positions of exposed finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the Architect.

5. These drawings are not to be used for construction unless noted below as "Issuance: For Construction"

All work is to be carried out in conformance with the Code and Bylaws of the authorities having jurisdiction.

7. The Architect of these plans and specifications gives no warranty or representation to any party about the constructability of the building(s) represented by them. All contractors or subcontractors must satisfy themselves when bidding and at all times ensure that they can properly construct the work represented by these plans.

© architectsAlliance, 2021

| NO | ISSUANCE | DATE |
|----|-------------|------|
| 1 | SPA/OPA/ZBA | - |
| 2 | - | - |
| 3 | - | - |
| 4 | - | - |
| 5 | _ | _ |



architectsAlliance

205 - 317 Adelaide Street West Toronto, ON M5V 1P9 Canada t 416 593 6500 f 416 593 4911 info@architectsalliance.com www.architectsalliance.com

Pier 27 Phase 3 (buildings F and A) 25&35 Queens Quay East

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, suite 308 Toronto M5E 1A7

| Context |
|-------------|
| Project No. |
| 1:500 |
| |

A.0.6



- 35 RESIDENTIAL PARKING SPACES UNDER BUILDING G
- 61 COMMERCIAL PARKING SPACES
- 104 RESIDENTIAL PARKING SPACES UNDER BUILDING A & F
- 344 RESIDENTIAL PARKING SPACES UNDER BUILDING B & D

EXISTING RESIDENTIAL PARKING
BUILDING B & D

RESIDENTIAL PARKING
BUILDING A & F

RESIDENTIAL PARKING BUILDING G

COMMERCIAL PARKING

 Copyright of this drawing is reserved by the Architect. The drawing and all associated documents are an instrument of service by the Architect. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Architect.

2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application, the Architect will provide written/graphic clarification or supplementary information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. The Contractor is to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the Architect before commencing any work.

4. Positions of exposed finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the Architect.

5. These drawings are not to be used for construction unless noted below as "Issuance: For Construction"

All work is to be carried out in conformance with the Code and Bylaws of the authorities having jurisdiction.

7. The Architect of these plans and specifications gives no warranty or representation to any party about the constructability of the building(s) represented by them. All contractors or subcontractors must satisfy themselves when bidding and at all times ensure that they can properly construct the work represented by these plans.

© architectsAlliance, 2021

| NO | ISSUANCE | DATE |
|----|-------------|------|
| 1 | SPA/OPA/ZBA | - |
| 2 | - | - |
| 3 | - | - |
| 4 | - | - |
| 5 | - | - |




architectsAlliance

205 - 317 Adelaide Street West Toronto, ON M5V 1P9 Canada t 416 593 6500 f 416 593 4911 info@architectsalliance.com www.architectsalliance.com

Pier 27 Phase 3 (buildings F and A) 25&35 Queens Quay East

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, suite 308 Toronto M5E 1A7

| Duna in at NI a | |
|-----------------|--|
| Project No. | |
| 1:400 | |



1. Copyright of this drawing is reserved by the Architect. The drawing and all associated documents are an instrument of service by the Architect. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Architect.

2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application, the Architect will provide written/graphic clarification or supplementary information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. The Contractor is to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the Architect before commencing any work.

4. Positions of exposed finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the Architect.

5. These drawings are not to be used for construction unless noted below as "Issuance: For Construction"

6. All work is to be carried out in conformance with the Code and Bylaws of the authorities having jurisdiction.

7. The Architect of these plans and specifications gives no warranty or representation to any party about the constructability of the building(s) represented by them. All contractors or subcontractors must satisfy themselves when bidding and at all times ensure that they can properly construct the work represented by these plans.

© architectsAlliance, 2021

EXISTING RESIDENTIAL PARKING

BUILDING B & D

BUILDING A & F

RESIDENTIAL PARKING

COMMERCIAL PARKING

| NO | ISSUANCE | DATE |
|----|-------------|------|
| 1 | SPA/OPA/ZBA | - |
| 2 | - | - |
| 3 | - | - |
| 4 | - | - |
| 5 | - | - |
| | | |




architectsAlliance

205 - 317 Adelaide Street West Toronto, ON M5V 1P9 Canada t 416 593 6500 f 416 593 4911 info@architectsalliance.com www.architectsalliance.com

Pier 27 Phase 3 (buildings F and A) 25&35 Queens Quay East

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, suite 308 Toronto M5E 1A7

| P3 |
|-------------|
| Project No. |
| 1:400 |
| |



contained therein may not be reproduced in whole or in part without prior written permission of the Architect.

2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written

 Copyright of this drawing is reserved by the Architect. The drawing and all associated documents are an instrument of service by the Architect. The drawing and the information

- 2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application, the Architect will provide written/graphic clarification or supplementary information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.
- Drawings are not to be scaled for construction. The Contractor is to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the Architect before commencing any work.
- 4. Positions of exposed finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the Architect.
- 5. These drawings are not to be used for construction unless noted below as "Issuance: For Construction"
- All work is to be carried out in conformance with the Code and Bylaws of the authorities having jurisdiction.
- 7. The Architect of these plans and specifications gives no warranty or representation to any party about the constructability of the building(s) represented by them. All contractors or subcontractors must satisfy themselves when bidding and at all times ensure that they can properly construct the work represented by these plans.

© architectsAlliance, 2021

| NO | ISSUANCE | DATE |
|----|-------------|------|
| 1 | SPA/OPA/ZBA | - |
| 2 | - | - |
| 3 | - | - |
| 4 | - | - |
| 5 | - | - |

aA


architectsAlliance

205 - 317 Adelaide Street West Toronto, ON M5V 1P9 Canada t 416 593 6500 f 416 593 4911 info@architectsalliance.com www.architectsalliance.com

Pier 27 Phase 3 (buildings F and A) 25&35 Queens Quay East

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, suite 308 Toronto M5E 1A7

| P2 | |
|-------------|--|
| Project No. | |
| 1:400 | |
| | |



- 79 COMMERCIAL PARKING SPACES UNDER BUILDING G
- 31 COMMERCIAL PARKING SPACES UNDER BUILDING A & F
- 112 TOTAL COMMERCIAL PARKING SPACES
 ON P1 LEVEL
- 2 DAYCARE PARKING SPACES
- 36 RESIDENTIAL VISITOR PARKING SPACES UNDER BUILDING A & F
- 158 RESIDENTIAL PARKING SPACES UNDER BUILDING B & G
- EXISTING RESIDENTIAL PARKING
 BUILDING B & D
- COMMERCIAL / VISITOR PARKING

- Copyright of this drawing is reserved by the Architect. The drawing and all associated documents are an instrument of service by the Architect. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Architect.
- 2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application, the Architect will provide written/graphic clarification or supplementary information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.
- Drawings are not to be scaled for construction. The Contractor is to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the Architect before commencing any work.
- 4. Positions of exposed finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the Architect.
- 5. These drawings are not to be used for construction unless noted below as "Issuance: For Construction"
- 6. All work is to be carried out in conformance with the Code and Bylaws of the authorities having jurisdiction.
- 7. The Architect of these plans and specifications gives no warranty or representation to any party about the constructability of the building(s) represented by them. All contractors or subcontractors must satisfy themselves when bidding and at all times ensure that they can properly construct the work represented by these plans.

© architectsAlliance, 2021

| NO | ISSUANCE | DATE |
|----|-------------|------|
| 1 | SPA/OPA/ZBA | - |
| 2 | - | - |
| 3 | - | - |
| 4 | - | - |
| 5 | - | - |




architectsAlliance

205 - 317 Adelaide Street West Toronto, ON M5V 1P9 Canada t 416 593 6500 f 416 593 4911 info@architectsalliance.com www.architectsalliance.com

Pier 27 Phase 3 (buildings F and A) 25&35 Queens Quay East


Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, suite 308 Toronto M5E 1A7

| P1 |
|-------------|
| Project No. |
| 1:400 |



BUILDING F

BUILDING A



 Copyright of this drawing is reserved by the Architect. The drawing and all associated documents are an instrument of service by the Architect. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Architect.

2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application, the Architect will provide written/graphic clarification or supplementary information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.

3. Drawings are not to be scaled for construction. The Contractor is to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the Architect before commencing any work.

4. Positions of exposed finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the Architect.

5. These drawings are not to be used for construction unless noted below as "Issuance: For Construction"

All work is to be carried out in conformance with the Code and Bylaws of the authorities having jurisdiction.

7. The Architect of these plans and specifications gives no warranty or representation to any party about the constructability of the building(s) represented by them. All contractors or subcontractors must satisfy themselves when bidding and at all times ensure that they can properly construct the work represented by these plans.

© architectsAlliance, 2021

| O | ISSUANCE | DATE |
|----------|-------------|------|
| | SPA/OPA/ZBA | - |
| | - | - |
| | - | - |
| | - | - |
| | - | - |



architectsAlliance


205 - 317 Adelaide Street West Toronto, ON M5V 1P9 Canada t 416 593 6500 f 416 593 4911 info@architectsalliance.com www.architectsalliance.com

Pier 27 Phase 3 (buildings F and A) 25&35 Queens Quay East

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, suite 308 Toronto M5E 1A7

| Section |
|-------------|
| Project No. |
| 1:350 |
| |

A.3.1



 Copyright of this drawing is reserved by the Architect. The drawing and all associated documents are an instrument of service by the Architect. The drawing and the information contained therein may not be reproduced in whole or in part without prior written permission of the Architect.

2. These Contract Documents are the property of the Architect. The Architect bears no responsibility for the interpretation of these documents by the Contractor. Upon written application, the Architect will provide written/graphic clarification or supplementary information regarding the intent of the Contract Documents. The Architect will review Shop Drawings submitted by the Contractor for design conformance only.

Drawings are not to be scaled for construction. The Contractor is to verify all existing conditions and dimensions required to perform the work and report any discrepancies with the Contract Documents to the Architect before commencing any work.

4. Positions of exposed finished mechanical or electrical devices, fittings, and fixtures are indicated on architectural drawings. The locations shown on the architectural drawings govern over the Mechanical and Electrical drawings. Those items not clearly located will be located as directed by the Architect.

5. These drawings are not to be used for construction unless noted below as "Issuance: For Construction"

All work is to be carried out in conformance with the Code and Bylaws of the authorities having jurisdiction.

7. The Architect of these plans and specifications gives no warranty or representation to any party about the constructability of the building(s) represented by them. All contractors or subcontractors must satisfy themselves when bidding and at all times ensure that they can properly construct the work represented by these plans.

© architectsAlliance, 2021

| NO | ISSUANCE | DATE |
|----|-------------|----------|
| 1 | SPA/OPA/ZBA | - |
| 2 | - | - |
| 3 | - | - |
| 4 | - | - |
| 5 | _ | <u>-</u> |



architectsAlliance

205 - 317 Adelaide Street West Toronto, ON M5V 1P9 Canada t 416 593 6500 f 416 593 4911 info@architectsalliance.com www.architectsalliance.com

Pier 27 Phase 3 (buildings F and A) 25&35 Queens Quay East

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade, suite 308 Toronto M5E 1A7

| Section | |
|-------------|--|
| Project No. | |
| 1:350 | |

A.3.2



PROJECT MG4842

Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

MC CLYMONT & RAK ENGINEERS, INC.

STARTED September 21, 2020

WATER LEVEL:

2.55 m bgs

SHEET 1 OF 1

COMPLETED September 21, 2020 DATUM Geodetic SHEAR STRENGTH: Cu, KPa nat V - ♣ Q - ¥ rem V - ● U - ▲ ORGANIC VAPOUR READINGS SOIL PROFILE SAMPLES **30RING METHOD** DEPTH SCALE (metres) (ppm) \otimes ADDITIONAL LAB. TESTING PIEZOMETER STRATA PLOT 400 80 BLOWS/0.3m 100 200 300 20 40 OR STANDPIPE NUMBER TYPE ELEV. % LEL - (hexane) WATER CONTENT, PERCENT **DESCRIPTION** INSTALLATION DEPTH (m) 40 20 30 20 60 80 10 GROUND SURFACE 76.93 Flush Mount STRAIGHT DRILLING TO 3.96 m DEPTH 76.63 Bentonite 1.52 m Long 50 mm IØ6.02 PVC Riser Silica Sand HOLLOW STEM AUGER POWER BORING 3.05 m Long 50 mm ID Well Screen ∇ 72.97 72.97 3.96 End of Borehole. -4 1) Borehole remained dry on completion of drilling.
2) Water level was measured at 2.55 m depth on September 28, 2020 MCR LOG ENVIRONMENTAL 4842.GPJ 10/14/20 **GROUNDWATER ELEVATIONS** $\ensuremath{\,igspace \,}$ shallow/single installation ▼ DEEP/DUAL INSTALLATION LOGGED

WATER LEVEL:

CHECKED :

NS

MG4842 PROJECT

Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

MC CLYMONT & RAK ENGINEERS, INC.

September 21, 2020 STARTED

SHEET 1 OF 1 COMPLETED : September 21, 2020 DATUM Geodetic

| | Ĭ | SOIL PROFILE | F | | | MPL | | (ppi | | | | \otimes | | nat V rem V | ENGTH | | Q - X U - A | ING | PIEZOMETER |
|--------------|-------------------|--|---------------------|-----------------------|--------|------|------------|---------|----------|--------|-----------|-----------|-----------------|----------------|--------|--------|------------------------------|----------------------------|---|
| (sanauı) | BORING METHOD | DESCRIPTION | STRATA PLOT | ELEV. DEPTH (m) | NUMBER | TYPE | BLOWS/0.3m | % L | .EL - (h | exane) | 600 60 | 400 | WA ⁻ | TER C | ONTENT | Γ, PER | 80 CENT -I wl 40 | ADDITIONAL LAB. TESTING | OR STANDPIPE INSTALLATIO |
| | | GROUND SURFACE | ×××× | 76.93 | | | | | | | | | | | | | | | Elizab Mazzat |
| | | FILL: sand and silt, trace clay and organics, brown, moist, loose to compact | | | 1 | ss | 15 0 | 0 ≱ | | | | | | | | | | | Flush Mount Cover Bentonite |
| | | | | | 2 | ss | 10 | 40 ⊗ | | | | | | | | | | | 1.52 m Long 50 mm ID PVC Riser |
| | | | | | 3 | ss | 3 | 50 ⊗ | | | | | | | | | | | |
| | | - decayed wood at 2.44 m depth | | | 4 | SS | 25 | 30 ⊗ | | | | | | | | | | | |
| | | | | | 5 | SS | 7 | 40 ⊗ | | | | | | | | | | | |
| | | SAND: medium to fine, dark brown to black, wet, loose | | _ 72.66 4.27 | | | | 77 | | | | | | | | | | | |
| | | | | | 6 | SS | 9 | 7! ⊗ | p | | | | | | | | | | |
| RING | A AUGER | SILT: | | _ 70.83. 6.10 | | | | 25 | | | | | | | | | | | |
| POWER BORING | HOLLOW STEM AUGER | some fine sand, dark brown to black, wet, soft | | | 7 | SS | 4 | 35 ⊗ | | | | | | | | | | | |
| | | SILTY CLAY: trace sand, gravel and shells, black to grey, moist, soft to hard | | _ 69.31 7.62 | 8 | ss | 3 | | 130 ⊗ | | | | | | | | | | $\overline{\Delta}$ |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | 9 | SS | 3 | | 140 ⊗ | | | | | | | | | | 67.18 |
| | | | | | | | | | | | | | | | | | | | Silica Sand 66.26 |
| | | | | | 10 | SS | 4 | 60 ⊗ | | | | | | | | | | | |
| 2 | | WEATHERED SHALE: grey, moist | | _ 65.04 11.89 | | | | 0 | | | | | | | | | | | 3.05 m Loanog4 50 mm ID Well Screen |
| | | End of Borehole. | - - 4 | _ 64.05. 12.88 | 11 | SS | >100 | Ď | | | | | | | | | | | Well Screen 64.13. |
| | | Note: 1) Borehole remained dry on completion of drilling. 2) Water level was measured at 11.29 m depth on September 28, 2020 | | | | | | | | | | | | | | | | | |

WATER LEVEL: 7.46 m bgs WATER LEVEL:

CHECKED : NS

MG4842 PROJECT

Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

STARTED September 25, 2020

SHEET 1 OF 1

MC CLYMONT & RAK ENGINEERS, INC.

COMPLETED : September 25, 2020 DATUM Geodetic

| <u> </u> | 9 | HOD | SOIL PROFILE | | | SA | MPL | | | om) | , VAP | OUR | KEAL | DINGS ⊗ | SHEA | nat V rem V | =NGTH - | 1: Cu, 1 | KPa Q - X U - ▲ | P _R | DIEZOMETED |
|-------------------------|--------------|-------------------|---|-------------|---------------|--------|------|------------|---------|-------|-------|------|------|------------|-----------------|----------------|------------|----------|-------------------------------------|----------------------------|---|
| DEPTH SCALE (metres) | | ME | | STRATA PLOT | ELEV. | ER | וט | BLOWS/0.3m | | | 200 | 300 |) 4 | 100 | 2 | 20 · | 10 | 60 | 80 | ADDITIONAL LAB. TESTING | PIEZOMETER OR |
| <u>-</u> E | | בי אווא | DESCRIPTION | ATA | DEPTH | NUMBER | TYPE |)WS/ | % | LEL - | (hexa | ne) | | | WA ⁻ | | NTEN | T, PEF | RCENT —I wi | AB. T | STANDPIPE INSTALLATION |
| - | Č | P.C | | STR | (m) | Ž | | BLC | | 20 | 40 | 60 | | 80 | | | 20 | 30 | 40 | ``` | |
| | | | GROUND SURFACE | | 76.08 | | | | | | | | | | | | | | | | |
| | | | FILL: sand and gravel, trace organics, brown, moist, loose | \bowtie | | | | | | | | | | | | | | | | | Flush Mount Cover |
| | | | | | | 1 | ss | 16 0 | þ Þ | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | Bentonite |
| | | | | \bowtie | | | | | | | | | | | | | | | | | 1 52 m Leng- |
| | | | | \bowtie | | | | | 20 ⊗ | | | | | | | | | | | | 1.52 m Logg ₇ 50 mm ID PVC Riser |
| | | | | \bowtie | | 2 | SS | 9 | ⊗ | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | 74.56 Silica Sand |
| | ניז | GER | | | | | | | 45 | | | | | | | | | | | | |
| | RIN | M AU | | \bowtie | | 3 | ss | 4 | 15 ⊗ | | | | | | | | | | | | Silica Sand |
| 2 | R BC | STE | | | | | | | | | | | | | | | | | | | 3.05 m Long |
| | POWER BORING | HOLLOW STEM AUGER | | \bowtie | | | | | | | | | | | | | | | | | 3.05 m Long 50 mm ID Well Screen |
| | п. | HOL | | \bowtie | | | | | | | | | | | | | | | | | 3.05 m Long 50 mm ID Well Screen |
| | | | - wet and brick fragments at 2.59 m depth | \bowtie | | 4 | SS | 6 | 20 ⊗ | | | | | | | | | | | | |
| | | | | | | ľ | | ŭ | ľ | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | 30 ⊗ | | | | | | | | | | | | |
| | | | | | | 5 | SS | 5 | 8 | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| 4 | | | | \bowtie | | | | | | | | | | | | | | | | | |
| . | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | 71.51 | | | | | | | | | | | | | | | | 71.51 |
| İ | | | SANDY SILT: dark brown to grey, moist to wet, stiff | | 4.57 | | | | | | | | | | | | | | | | |
| | | | 3.7, | | | 6 | SS | 17 | 30 ⊗ | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | End of Borehole. | | 70.90 5.18 | | | | | | | | | | | | | | | | |
| | | | Note: | | | | | | | | | | | | | | | | | | |
| | | | Borehole remained dry on completion of drilling. Water level was measured at 2.71 m depth on September 28, 2020 | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | GROUNDWATER ELEVATION | | | | | | | | | | | | | | | | | | |
| | | | $\overline{igspace}$ shallow/single installatio | N | | | | | JAL I | NST. | ALL | ATIC | N | | | LOGG | ED : | PL | | | |
| | | | WATER LEVEL: 2.71 m bgs | | V | VAT | ER L | EVE | EL: | | | | | | | CHEC | KED : | NS | 3 | | |

PROJECT : MG4842

LOCATION : Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario

MC CLYMONT & RAK ENGINEERS, INC.

STARTED : September 22, 2020 COMPLETED : September 22. 2020

SHEET 1 OF 1
DATUM Geodetic

| SOIL PROFILE SAMPLES ORGANIC VAPOUR READINGS (ppm) SHEAR STRENGTH: nat V - ● 100 200 300 400 20 40 60 80 WATER CONTENT wp - ● W 100 200 300 400 20 40 60 80 WATER CONTENT wp - ● W 100 20 30 40 60 80 10 20 30 30 40 WATER CONTENT wp - ● W 100 20 30 40 60 80 10 20 30 30 40 WATER CONTENT wp - ● W 100 20 30 40 60 80 10 20 30 30 40 WATER CONTENT : Cu, KPa Q - X | (1) |
|--|---------------------------|--|
| T | 11 🛦 | 1 (9 1 |
| 181 181 19 <u>1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 </u> | 60 80 | PIEZOMETER OR STANDPIPE INSTALLATIO |
| DESCRIPTION DESCR | T, PERCENT | OR STANDPIPE |
| DESCRIPTION V | 1 wl 30 40 | INSTALLATIO |
| 00 | 1 1 | |
| FILL: | | |
| sand and gravel, brown, moist, compact to loose 1 SS 26 9 | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| 3 SS 4 | | |
| | | |
| | | |
| | | |
| FILL: Clay and silt, some organics, trace of sand and gravel, dark brown to black, moist, loose 4 SS 9 8 | | |
| gravel, dark brown to black, moist, loose | | |
| | | |
| To clay and silt, some organics, trace of sand and gravel, dark brown to black, moist, loose 4 SS 9 8 | | |
| S SS 12 S SS 12 S S S S S S S S S | | |
| | | |
| | | |
| | | |
| | | |
| SILTY CLAY: trace sand and gravel, black to grey, moist, stiff | | |
| trace sailu and graver, brack to grey, moist, suin | | |
| | | |
| 6 SS 5 6 | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| 7 SS 13 6 | | |
| 7 SS 13 Ø | | |
| 70.17 End of Borehole. | | |
| Note: | | |
| 1) Borehole remained dry on completion of drilling. | | |
| | | |
| | | |
| | | |
| | | |
| GROUNDWATER ELEVATIONS | | |
| ☐ SHALLOW/SINGLE INSTALLATION ☐ DEEP/DUAL INSTALLATION LOGGED : | PL | |
| WATER LEVEL: m bgs WATER LEVEL: CHECKED : | | |

PROJECT MG4842

Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

MC CLYMONT & RAK ENGINEERS, INC.

STARTED September 24, 2020

WATER LEVEL:

m bgs

SHEET 1 OF 1

COMPLETED September 24, 2020 DATUM Geodetic SHEAR STRENGTH: Cu, KPa nat V - Q - Q rem V - U - A ORGANIC VAPOUR READINGS SOIL PROFILE SAMPLES **30RING METHOD** DEPTH SCALE (metres) (ppm) \otimes ADDITIONAL LAB. TESTING PIEZOMETER 400 80 STRATA PLOT 200 300 20 40 100 OR STANDPIPE NUMBER TYPE ELEV. BLOWS/0. % LEL - (hexane) WATER CONTENT, PERCENT **DESCRIPTION** INSTALLATION DEPTH (m) 20 30 80 10 GROUND SURFACE 75.84 75 mm ASPHALT 75.76 0.08 425 mm GRANULAR FILL: sand and gravel, trace of organics, brown, moist, compact. SS 27 🕏 sandy and silt, trace organics and gravel, black, moist, compact SS 11 8 HOLLOW STEM AUGER POWER BORING 74.01 1.83 3 ss 6 silt and clay, trace organics and sand, black, moist, loose -2 ss 4 🕏 20 ⊗ 72.49 3.35 5 SS 2 SILTY CLAY: trace sand and gravel, black to grey, moist to wet, soft -4 MCR LOG ENVIRONMENTAL 4842.GPJ 10/14/20 71.27 4.57 End of Borehole. Borehole remained dry on completion of drilling. SS 3 **GROUNDWATER ELEVATIONS** abla shallow/single installation ▼ DEEP/DUAL INSTALLATION LOGGED

WATER LEVEL:

CHECKED :

NS

MG4842 PROJECT

Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

September 23, 2020 STARTED

SHEET 1 OF 1

MC CLYMONT & RAK ENGINEERS, INC.

| | 오 | | SOIL PROFILE | | | SA | MPL | ES | | RGANIC pm) | VAP | OUR F | READ | DINGS ⊗ | SHEA | R STI nat rem | RENGT V - ♣ V - ● | H: Cu, | , KPa Q - U - | × | YG. | |
|----------|---------------|-------------------|---|-------------|------------------|--------|------|------------|---------|---------------|------|-------|------|------------|---------|---------------------|---------------------------------------|---------|---------------------|---------|----------------------------|---|
| (metres) | BORING METHOD | | | STRATA PLOT | | Ľ. | | .3m | L | 100 | 200 | 300 | 4 | 100 | 2 | 20 | 40 | 60 | 80 | | ADDITIONAL LAB. TESTING | PIEZOMETER OR |
| (met | Ŋ | | DESCRIPTION | TAF | ELEV. DEPTH | NUMBER | TYPE | BLOWS/0.3m | % | LEL - (| hexa | ne) | | | | | ONTE | IT, PE | | NT | DDIT B. TE | STANDPIPE INSTALLATIO |
| | BOR | | | STRA | (m) | Ŋ | | BLO | | 20 | 40 | 60 | | 80 | wp 1 | I— | 20 | 30 | — I v 40 | vl | ₹₹ | |
| ╛ | | 1 | GROUND SURFACE | | 77.03 | | | | | | | | | | | | | | | | | |
| | | ŀ | 75 mm ASPHALT 425 mm GRANULAR FILL: | • | 76.95 | 1 | ss | 140 | 0 | | | | | | | | | | | | | Flush Mount Cover |
| | | | sand and gravel, trace of organics, brown, moist, compact. | / 🔆 | _ 76.53. 0.50 | | | | | | | | | | | | | | | | | Bentonite |
| | | ı | FILL: sandy and silt, trace organics and gravel, black, | | | 2 | ss | 6 | 10 ⊗ | | | | | | | | | | | | | 1.52 m Long 50 mm ID |
| | | | moist, loose | | | | | - | | | | | | | | | | | | | | PVC Riser |
| | | | | \bowtie | _ 75.20 1.83 | 3 | ss | 3 | 10 ⊗ | | | | | | | | | | | | | |
| | | | FILL: silt and clay, trace organics and sand, black, moist, | | 1.03 | | | | | | | | | | | | | | | | | |
| | | | loose | | | 4 | SS | 3 (| 5 Ø | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | |
| | | | - brick fragments at 3.35 m depth | \bowtie | | 5 | SS | 2 | 10 ⊗ | | | | | | | | | | | | | |
| | | | - blick fragments at 3.33 m depth | | | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | | |
| | | ŀ | SANDY SILT: | | _ 72.68 4.35 | | | | | | | | | | | | | | | | | |
| | | | trace organics and gravel, dark brown to black, wet, stiff | | | 6 | ss | 3 | | 130 ⊗ | ' | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | |
| | | SER. | | | | | | | | | | | | | | | | | | | | |
| | POWER BORING | HOLLOW STEM AUGER | | | | | | | | _ | | | | | | | | | | | | |
| | R BO | STEN | | | | 7 | ss | 12 | | 70 9 | | | | | | | | | | | | |
| | OWE | 8 | | | | | | | | | | | | | | | | | | | | |
| | | 킭 | | | | | | | | | | | | | | | | | | | | |
| | | ╌┞ | SILTY CLAY: | | 69.41 7.62 | | | | | | | | | | | | | | | 40 | • | |
| | | | trace of sand and gravel, grey, moist to wet, soft | | 7.02 | 8 | ss | 3 | 20 ⊗ | | | | | | | | | | | 46 O | 6 | |
| | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | 10 | | | | | | | | | | | | | |
| | | | | | | 9 | SS | 2 | ⊗ັ | | | | | | | | | | | | | 67.58 |
| ا ٥ | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | Silica Sand :: |
| | | | | | | | | | 5 | | | | | | | | | | | | | |
| | | | | | | 10 | SS | 4 | 5 Ø | | | | | | | | | | | | | $\overline{\Delta}$ |
| | | | | | | | | | | | | | | | | | | | | | | |
| 2 | | | | | | | | | | | | | | | | | | | | | | 65.14 |
| - | | | | | | | 00 | | p p | | | | | | | | | | | | | |
| | | | | | | 11 | SS | 4 0 | | | | | | | | | | | | | | : · · · · · · · · · · · · · · · · · · · |
| | | | | | | | | | | | | | | | | | | | | | | 3.05 m Long 50 mm l@3.62 |
| | | ŀ | WEATHERED SHALE: | | 63.62 13.41 | | | | | | | | | | | | | | | | | 50 mm l 3.62 Well Screen |
| 4 | | | grey, moist | A | _ 63.01 14.02 | 12 | 99 | >10@ | 0 | | | | | | | | | | | | | |
| ۱ | | | End of Borehole. | | 14.02 | 12 | 33 | 100 | | | | | | | | | | | | | | |
| | | | Note: 1) Borehole remained dry on completion of drilling. 2) Water level was measured at 11.29 m depth on | | | | | | | | | | | | | | | | | | | |
| | | | 2) Water level was measured at 11.29 m depth on September 28, 2020 | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | \perp | | | | |
| | | | GROUNDWATER ELEVATION | | | | | | | | | | | | | | | | | | | |
| | | | abla shallow/single installatio | N | lacksquare | וח | EEP | וח/י | IAI | INSTA | 1112 | ΔTIO | N | | | | GED | : P | | | | |

MG4842 PROJECT

Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

MC CLYMONT & RAK ENGINEERS, INC.

September 23, 2020 STARTED

SHEET 1 OF 1 September 23, 2020 COMPLETED DATUM Geodetic

| | | SOIL PROFILE | | | | MDI | | ORGANIC | VAPOL | JR REAL | DINGS | SHEA | R STR | ENGTH: | Cu, KI | Pa | | |
|----------|-----------------------------------|---|---------------|---------------|--------|------|------------|------------|--------|---------|-----------|------|----------------|----------------------|---------|----------------|----------------------------|---|
| (metres) | BORING METHOD | SOIL PROFILE | <u> </u> | i | SA | MPL | _ | (ppm) | - | | \otimes | | nat V rem V | ENGTH: - • - • | (| Q - 🗶 U - 🔺 | ADDITIONAL LAB. TESTING | PIEZOMETER |
| tres) | MET | | STRATA PLOT | | 유 | | BLOWS/0.3m | 100 2 | 00 : | 300 4 | 100 I | 2 | :0 · | 40 6 | 60 I | 80 | NOI | OR STANDPIPE |
| (me | NG | DESCRIPTION | TAF | ELEV. | NUMBER | TYPE | VS/C | % LEL - (h | exane) | | | WAT | ER CO | ONTENT | , PERO | | 3. TE | STANDPIPE INSTALLATIO |
| | ORI | | IRA. | DEPTH (m) | 2 | - | NO/ | 20 | 10 | 60 | 80 | wp | 0 : | 20 3 | 30 | ⊣ wl 40 | [F F | IIIO IALLA IIO |
| | <u> </u> | GROUND SURFACE | S. | | Н | | ш | 20 | 40 | 60 | 80 | | | Ť | 1 | + | | |
| | | STRAIGHT DRILLING TO 4.27 m DEPTH | | 77.03 | H | | | | | | | | | | | | | Flush Mount |
| | | | | | | | | | | | | | | | | | | Cover |
| | | | \otimes | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | Bentonite 76.43 |
| | | | | | | | | | | | | | | | | | | <u> </u> |
| | | | | | | | | | | | | | | | | | | |
| | | | \bowtie | | | | | | | | | | | | | | | 1.52 m Long 50 mm ID PVC Riser |
| | | | | | | | | | | | | | | | | | | PVC Riser : |
| | | | | | | | | | | | | | | | | | | |
| | | | \bowtie | | | | | | | | | | | | | | | 75.81 |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | Silica Sand |
| | | | \bowtie | | | | | | | | | | | | | | | Siliou Garia |
| | <u> </u> | | | | | | | | | | | | | | | | | |
| | POWER BORING HOLLOW STEM AUGER | | | | | | | | | | | | | | | | | Silica Sand 3.05 m Long 50 mm ID Well Screen |
| | POWER BORING LLOW STEM AUG | | | | | | | | | | | | | | | | | : |
| | ER E | | | | | | | | | | | | | | | | | 3.05 m Long |
| | NO NO | | | | | | | | | | | | | | | | | 3.05 m Long 50 mm ID Well Screen |
| | 뉴 로 | | | | | | | | | | | | | | | | | |
| | | | \bowtie | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | <u> </u> |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | l :E |
| | | | | | | | | | | | | | | | | | | ·:= |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | \bowtie | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | \bowtie | | | | | | | | | | | | | | | 72.76 |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | :: |
| | \vdash | End of Rorahola | _ XXX | 72.76 4.27 | | | | | | | | | | | | | | 72.76 |
| | | End of Borehole. | | | | | | | | | | | | | | | | |
| | | Note: 1) Borehole remained dry on completion of drilling. | | | | | | | | | | | | | | | | |
| | | Borehole remained dry on completion of drilling. Water level was measured at 2.55 m depth on September 28, 2020 | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | |
| | | |)//C | <u> </u> | Ш | | | | | 1 | 1 | | | | | 1 | | |
| | | GROUNDWATER ELEVATION | | | | | | | | | | | | | | | | |
| | | $\overline{igspace}$ shallow/single installation | NC | | | | | AL INSTA | LLAT | ION | | | LOGG | ED : | PL | | | |
| | | WATER LEVEL: 2.55 m bas | | | VATE | -D I | | 1. | | | | | CHEC | | NC | | | |

WATER LEVEL: 2.55 m bgs WATER LEVEL:

CHECKED : NS

PROJECT : MG4842

LOCATION : Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario

MC CLYMONT & RAK ENGINEERS, INC. SHEET 1 OF 1

STARTED : September 22, 2020 COMPLETED : September 22, 2020

September 22, 2020 DATUM Geodetic

PROJECT : MG4842

LOCATION : Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario

MC CLYMONT & RAK ENGINEERS, INC. SHEET 1 OF 1

STARTED : September 24, 2020 COMPLETED : September 24, 2020

DATUM Geodetic

| CO | MF | PLE | TED : September 24, 2020 | | | | | | | | | | | | | | | | DATUM | Geod | etic |
|----------|--------------|-------------------|---|-------------|---------------|--------|------|------------|------------|---------|--------|--------|-------------|------|----------------|---------------------|----------|--------------------|----------------------------|----------|---------------------------------------|
| | 2 | a O | SOIL PROFILE | | | SA | MPL | .ES | ORC (pp | | VAPOL | JR REA | ADINGS ⊗ | SHEA | R STR nat V | ENGTH - 🖶 - 🍑 | : Cu, k | Pa Q - X | ي ا | | |
| (metres) | Ē | BORING METHOD | | TO | | ~ | | 3m | | | 00 : | 300 | 400 |] 2 | rem V 20 - | - • 40 | 60 | U - ▲ 80 | ADDITIONAL LAB. TESTING | PI | EZOMETER OR TANDPIPE |
| metr | 0 | 2 | DESCRIPTION | P PI | ELEV. | NUMBER | TYPE | /S/0. | % I | EL - (h | exane) | | | WA | TER CO | NTENT | , PER | CENT | T E E | S | TANDPIPE |
| | ٥ | באר באר | | STRATA PLOT | DEPTH (m) | Š | ← | BLOWS/0.3m | _ | 00 | 10 | 60 | 80 | wp | 10 | 0 W | 30 | ⊣ wl 40 | A B | line | STALLATION |
| \dashv | _ | n | GROUND SURFACE | S | | | | ш | - | 20 4 | 40 | 60 | 80 | | 10 . | - | + | + | | | |
| 1 | | | STRAIGHT DRILLING TO 4.57 m DEPTH | | 77.06 | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | 76.46 |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | 75.04 |
| | | | | | | | | | | | | | | | | | | | | | 75.84 |
| | | | | | | | | | | | | | | | | | | | 1 | | 1 |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | 1 | | E |
| | | 2 | | \bowtie | | | | | | | | | | | | | | | | | |
| | NG. | NGE | | \bowtie | | | | | | | | | | | | | | | | | |
| | ORI | EM A | | \bowtie | | | | | | | | | | | | | | | | | |
| | POWER BORING | STE | | \bowtie | | | | | | | | | | | | | | | | | |
| | ωo | POM | | \bowtie | | | | | | | | | | | | | | | | | |
| ľ | ш | HOLLOW STEM AUGER | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | : |
| | | | | \bowtie | | | | | | | | | | | | | | | | ∇ | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | · · · · · · · · · · · · · · · · · · · |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | \bowtie | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | į |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | 1 | | • |
| | | | | | | | | | | | | | | | | | | | 1 | | 72 40 |
| ŀ | | \Box | End of Borehole. | T*** | 72.49 4.57 | | | | | | | | | | | | | | 1 | | 72.49 : - |
| | | | Note: | | | | | | | | | | | | | | | | 1 | | |
| | | | Borehole remained dry on completion of drilling. Water level was measured at 2.84 m depth on September 28, 2020 | | | | | | | | | | | | | | | | 1 | | |
| | | | | | | | | | | | | | | | | | | | | | |
| | | | GROUNDWATER ELEVATION \overline{Y} SHALLOW/SINGLE INSTALLATION | | | | ==- | יחע | 1A1 IN | NSTA | 11 ^ 7 | יאטוי | | | | | _ | | | | |
| | | | WATER LEVEL: 2.84 m bgs | /IN | | VATI | | | | NOIA | LLAI | ION | | | LOGG | | PL NS | | | | |

PROJECT: MG4842

STARTED

COMPLETED

LOCATION : Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario

September 22, 2020 SHEET 1 OF 1
September 22, 2020 DATUM Geodetic

MC CLYMONT & RAK

ENGINEERS, INC.

SHEAR STRENGTH: Cu, KPa nat V - • Q - X rem V - • U - • ORGANIC VAPOUR READINGS SOIL PROFILE SAMPLES **30RING METHOD** DEPTH SCALE (metres) (ppm) \otimes ADDITIONAL LAB. TESTING PIEZOMETER 400 80 STRATA PLOT 200 20 40 100 300 OR NUMBER TYPE ELEV. STANDPIPE BLOWS/0 % LEL - (hexane) WATER CONTENT, PERCENT **DESCRIPTION** INSTALLATION DEPTH (m) 20 30 40 20 60 80 10 GROUND SURFACE 77.06 FILL: sandy and silt, trace organics and gravel, black, moist, dense to loose Flush Mount SS 55.0 Bentonite l⊗²⁰ 1.52 m Long 50 mm ID PVC Riser 2 SS 11 10 ⊗ 75.23 1.83 3 SS 5 FILL: silt and clay, trace organics and sand, black, moist, 2 loose 45 ⊗ SS 4 3 50 5 SS 3 Ø - wood fragments at 4.57 m depth 30 ⊗ SS 6 HOLLOW STEM AUGER POWER BORING -6 70.96 6.10 SILTY CLAY: trace of sand and gravel, grey, moist to wet, soft 30 ⊗ SS 5 69.44 7.62 SANDY SILT: 30 ⊗ trace organics and clay, dark brown to black, wet, soft SS -8 67.92 9.14 SILTY CLAY: trace of sand and gravel, grey, moist, soft SS 4 10 Silica Sand 66.39 45. O 10 SS 2 12 64.87 MCR LOG ENVIRONMENTAL 4842.GPJ 10/15/20 SS >100 WEATHERED SHALE: grey, moist End of Borehole. 3.05 m Long 50 mm ID Well Screen 1) Borehole remained dry on completion of drilling.
2) Water level was measured at 9.80 m depth on September 28, 2020 **GROUNDWATER ELEVATIONS** abla shallow/single installation ▼ DEEP/DUAL INSTALLATION LOGGED WATER LEVEL: WATER LEVEL: 9.80 m bgs CHECKED : NS

PROJECT MG4842

Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

ENGINEERS, INC. SHEET 1 OF 1

September 23, 2020 STARTED

WATER LEVEL:

m bgs

MC CLYMONT & RAK

COMPLETED September 23, 2020 DATUM Geodetic SHEAR STRENGTH: Cu, KPa nat V - Q - Q rem V - U - A ORGANIC VAPOUR READINGS SAMPLES SOIL PROFILE **30RING METHOD** DEPTH SCALE (metres) (ppm) \otimes ADDITIONAL LAB. TESTING PIEZOMETER 400 80 STRATA PLOT 200 300 20 40 100 OR STANDPIPE NUMBER TYPE ELEV. BLOWS/0. % LEL - (hexane) WATER CONTENT, PERCENT **DESCRIPTION** INSTALLATION DEPTH (m) 20 30 20 80 10 GROUND SURFACE 77.11 75 mm ASPHALT 77.03 0.08 425 mm GRANULAR FILL: sand and gravel, trace of organics, brown, moist, compact. SS 29 🕸 sandy and silt, trace organics and gravel, black, ss 2 8 HOLLOW STEM AUGER POWER BORING SS 12 🕏 75.28 1.83 FILL: silt and clay, trace organics and sand, black, moist, loose -2 20 ⊗ ss 4 20 ⊗ SS 4 10 8 SS 4 71.32 5.79 SANDY SILT: grey to black, wet, stiff -6 10 14 ⊗ SS 70.40 6.71 MCR LOG ENVIRONMENTAL 4842.GPJ 10/14/20 End of Borehole. Borehole remained dry on completion of drilling. **GROUNDWATER ELEVATIONS** abla shallow/single installation ▼ DEEP/DUAL INSTALLATION LOGGED

WATER LEVEL:

CHECKED :

NS

PROJECT MG4842


Pier 27, Yonge Street & Queens Quay East, Toronto, Ontario LOCATION

MC CLYMONT & RAK ENGINEERS, INC.

STARTED September 24, 2020

SHEET 1 OF 1 COMPLETED : September 24, 2020 DATUM Geodetic

| CC | MPLE | ETED : September 24, 2020 | | | | | | | | | | | | | | | | DATUM | Geodetic |
|-------------------------|---------------|---|-------------|---------------|--------|----------|------------|--------------|----------|--------|------|--------------|-----------------|----------------|---------------|----------|-------------------------------------|----------------------------|--|
| щ | dol | SOIL PROFILE | | | SA | MPL | ES | ORG/ (ppm | | /APOUF | R RE | ADINGS ⊗ | SHEA | R STR nat V | ENGTH | l: Cu, k | (Pa Q - X U - ∆ | ی ل | |
| DEFIN SCALE (metres) | BORING METHOD | | TO. | | ~ | | 3m | | | 00 30 | 00 | 400 | | rem V | - ● 40 | 60 | U - ▲ 80 | ADDITIONAL LAB. TESTING | PIEZOMETER |
| netre | IG M | DESCRIPTION | STRATA PLOT | ELEV. | NUMBER | TYPE | BLOWS/0.3m | | EL - (he | | | - | WA ⁻ | TER CO | NTEN. | T, PER | | J ESE | OR STANDPIPE |
| ت ز | JRIN | DECOMI HOM | RAT, | DEPTH (m) | NON | | ŏ. | | | | | | wp | - | ow | <u>'</u> | -l wl | ADI LAB. | INSTALLATIO |
| - | - BC | | ST | (m) | | | Щ | 20 |) 4 | 0 6 | 0 | 80 | | 10 | 20 | 30 | 40 | \perp | |
| | \vdash | GROUND SURFACE 75 mm CONCRETE | - | 77.05 | | | \sqcup | | | | _ | | _ | | | | | - | Flush Mount |
| | | 525 mm GRANULAR FILL: | • | 76.97 0.08 | | | | | | | | | | | | | | | Cover |
| | | sand and gravel, trace of organics, brown, moist, compact. | • (| • | 1 | | 23 0 | | | | | | | | | | | | |
| | | | | | ' | 33 | 23 4 | | | | | | | | | | | | |
| | | | • (| | | | | | | | | | | | | | | | Bentonite |
| | | FILL: | | 76.44 0.61 | | | | | | | | | | | | | | | |
| | | clayey silt with organics, trace of sand and gravel, trace of clinkers and brick pieces, black, moist, compact. | | | | | | | | | | | | | | | | | 4.50 |
| | | black, moist, compact. | | | | | | | | | | | | | | | | | 1.52 m Long ₄ 50 mm ID PVC Riser |
| | | | | | 2 | ss | 130 | | | | | | | | | | | | PVC Riser : |
| | | | \bowtie | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | 75.53 |
| | | | \bowtie | | | | | | | | | | | | | | | | 75.53 . · Silica Sand . · · |
| | | | | | | | | , | | | | | | | | | | | |
| | | | | | 3 | ss | 7 🕏 | | | | | | | | | | | | |
| 2 | | | | 1 | | | | | | | | | | | | | | | 3.0E m l ==== |
| | | | | | | | | | | | | | | | | | | | 3.05 m Long 50 mm ID |
| | | | | | | | | | | | | | | | | | | | ₩ell Screen : |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | <u> </u> | | | | | | | | | | | | |
| | | | | | 4 | SS | 5 🕏 | ' | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | 1 | | \vdash | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | 5 | ss | 3 0 | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | : |
| | | | | 1 | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | 1 | | | | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | | | | | | | | |
| | | | | 1 | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | CAND: | _₩ | 72.48 4.57 | | Ш | | | | | | | | | | | | | 72.48 |
| | | SAND: fine, some silt, trace gravel, grey, wet, very loose | | 4.57 | | | | | | | | | | | | | | | |
| | | | | : | 6 | SS | 3 0 | | | | | | | | | | | | |
| | | | | | υ | 33 | اً | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | End of Borehole. | + | 71.87 5.18 | | | | | | | | | | | | | | | |
| | | Note: | | | | | | | | | | | | | | | | | |
| | | 1) Borehole remained dry on completion of drilling. 2) Water level was measured at 2.25 m depth on September 28, 2020 | | | | | | | | | | | | | | | | | |
| | | September 28, 2020 | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | | | | | | | | |
| | | | \perp | <u>L</u> | L | | | | | | | | L | L | L | | | | |
| | | GROUNDWATER ELEVATION | ONS | ; | | | | | | | | • | | | | | • | • | |
| | | $\overline{igspace}$ SHALLOW/SINGLE INSTALLATION | | | יח | =FP | י וכו/י | AI IN | STAI | LLATI | ON | | | 1000 | ED . | Di | | | |
| | | WATER LEVEL: 2.25 m bgs | J. 1 | | | ER L | | | J 1 ∕\l | | JIN | | | LOGG | ED : KED : | PL NS | | | |
| | | | | • | | • - | | - | | | | | | UITEU | \LU . | ino | | | |





MCCLYMONT & RAK ENG. INC

ATTN: Richard Sukhu 111 ZENWAY BLVD.

UNIT 4

VAUGHAN ON L4H 3H9

Date Received: 30-SEP-20

Report Date: 09-OCT-20 12:10 (MT)

Version: FINAL

Client Phone: 416-675-0160

Certificate of Analysis

Lab Work Order #: L2510345

Project P.O. #: NOT SUBMITTED

Job Reference: G4842

C of C Numbers: 17-844660

Legal Site Desc:

Emily Smith Account Manager

[This report shall not be reproduced except in full without the written authority of the Laboratory.]

ADDRESS: 95 West Beaver Creek Road, Unit 1, Richmond Hill, ON L4B 1H2 Canada | Phone: +1 905 881 9887 | Fax: +1 905 881 8062

ALS CANADA LTD Part of the ALS Group An ALS Limited Company





L2510345 CONT'D....

Job Reference: G4842

PAGE 2 of 17

09-OCT-20 12:10 (MT)

Summary of Guideline Exceedances

| Guideline | | | | | | |
|------------|-----------------------|--|----------------------|--------|-----------------|------|
| ALS ID | Client ID | Grouping | Analyte | Result | Guideline Limit | Unit |
| (No pa | arameter exceedances) | narge Sewer By-Law 100-2016 (FEB 4,20 narge Sewer By-Law 100-2016 (FEB 4,20 | , | | | |
| L2510345-1 | BH20-5S | Cyanides | Cyanide, Total | 0.170 | 0.02 | mg/L |
| | | Total Metals | Manganese (Mn)-Total | 0.208 | 0.05 | mg/L |
| | | | Zinc (Zn)-Total | 0.065 | 0.04 | mg/L |

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D.... Job Reference: G4842 PAGE 3 of 17 09-OCT-20 12:10 (MT)

Physical Tests - WATER

| i ilyolodi 100to 117ti Ett | |
|----------------------------|-------------------------------------|
| | Lab ID L2510345-1 |
| | Sample Date 30-SEP-20 |
| | Sample ID BH20-5S |
| | Guide Limits |
| Analyte | Unit #1 #2 |
| рН | pH units 6.00- 6.0-9.5 8.01 11.5 |
| Total Suspended Solids | mg/L 350 15 7.6 |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 4 of 17

09-OCT-20 12:10 (MT)

Anions and Nutrients - WATER

| | | Sample | Lab ID e Date ple ID | L2510345-1 30-SEP-20 BH20-5S |
|-------------------------|------|-------------|----------------------------|------------------------------------|
| Analyte | Unit | Guide #1 | Limits #2 | |
| Fluoride (F) | mg/L | 10 | - | 0.73 DLDS |
| Total Kjeldahl Nitrogen | mg/L | 100 | - | 8.57 |
| Phosphorus, Total | mg/L | 10 | 0.4 | 0.122 |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D.... Job Reference: G4842 PAGE 5 of 17 09-OCT-20 12:10 (MT)

Cvanides - WATER

| Gyannado III/II EII | | | | |
|---------------------|------|-------------|--------------|------------|
| | | | Lab ID | L2510345-1 |
| | | Sampl | e Date | 30-SEP-20 |
| | | San | nple ID | BH20-5S |
| Analyte | Unit | Guide #1 | Limits #2 | |
| Cyanide, Total | mg/L | 2 | 0.02 | 0.170 |
| | | | | |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 6 of 17

09-OCT-20 12:10 (MT)

Bacteriological Tests - WATER

| | | Lab ID | L2510345-1 |
|----------|-----------|-------------------------|------------------------------------|
| _ | | | |
| 5 | ample | e Date | 30-SEP-20 |
| | Sam | ple ID | BH20-5S |
| | | | |
| C | Guide | Limits | |
| Unit | #1 | #2 | |
| CFU/100m | - | 200 | 1 |
| - | (Unit | Sam Guide Unit #1 | Sample ID Guide Limits Unit #1 #2 |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 7 of 17

09-OCT-20 12:10 (MT)

Total Metals - WATER

| | | Sampl | Lab ID e Date iple ID | L2510345-1 30-SEP-20 BH20-5S |
|-----------------------|------|-------------|-----------------------------|------------------------------------|
| Analyte | Unit | Guide #1 | Limits #2 | |
| Aluminum (Al)-Total | mg/L | 50 | - | 2.09 DLHC |
| Antimony (Sb)-Total | mg/L | 5 | - | 0.0019 ^{DLHC} |
| Arsenic (As)-Total | mg/L | 1 | 0.02 | 0.0091 ^{DLHC} |
| Cadmium (Cd)-Total | mg/L | 0.7 | 0.008 | 0.000067 ^{DLHC} |
| Chromium (Cr)-Total | mg/L | 4 | 0.08 | < 0.0050 DLHC |
| Cobalt (Co)-Total | mg/L | 5 | - | 0.0023 ^{DLHC} |
| Copper (Cu)-Total | mg/L | 2 | 0.04 | 0.0055 ^{DLHC} |
| Lead (Pb)-Total | mg/L | 1 | 0.12 | 0.0231 ^{DLHC} |
| Manganese (Mn)-Total | mg/L | 5 | 0.05 | 0.208 DLHC |
| Mercury (Hg)-Total | mg/L | 0.01 | 0.0004 | 0.0000227 |
| Molybdenum (Mo)-Total | mg/L | 5 | - | 0.00708 ^{DLHC} |
| Nickel (Ni)-Total | mg/L | 2 | 0.08 | 0.0063 ^{DLHC} |
| Selenium (Se)-Total | mg/L | 1 | 0.02 | < 0.00050 DLHC |
| Silver (Ag)-Total | mg/L | 5 | 0.12 | < 0.00050 DLHC |
| Tin (Sn)-Total | mg/L | 5 | - | 0.0011 ^{DLHC} |
| Titanium (Ti)-Total | mg/L | 5 | - | 0.0772 ^{DLHC} |
| Zinc (Zn)-Total | mg/L | 2 | 0.04 | 0.065 DLHC |
| | | | | |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D.... Job Reference: G4842 PAGE 8 of 17 09-OCT-20 12:10 (MT)

Speciated Metals - WATER

| | | 1 | Lab ID | L2510345-1 |
|----------------------|------|-------------|--------------|------------|
| | | Sample | e Date | 30-SEP-20 |
| | | Sam | iple ID | BH20-5S |
| Analyte | Unit | Guide #1 | Limits #2 | |
| Chromium, Hexavalent | mg/L | 2 | 0.04 | <0.00050 |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 9 of 17

09-OCT-20 12:10 (MT)

Aggregate Organics - WATER

| | | Sample | Lab ID e Date ple ID | L2510345-1 30-SEP-20 BH20-5S |
|-------------------------|------|-------------|----------------------------|------------------------------------|
| | | Jaii | ibie in | БП20-33 |
| Analyte | Unit | Guide #1 | Limits #2 | |
| BOD | mg/L | 300 | 15 | <3.0 BODL |
| Oil and Grease, Total | mg/L | - | - | <5.0 |
| Animal/Veg Oil & Grease | mg/L | 150 | - | <5.0 |
| Mineral Oil and Grease | mg/L | 15 | - | <2.5 |
| | | | | |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law

Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 10 of 17

09-OCT-20 12:10 (MT)

Volatile Organic Compounds - WATER

| Lab ID | L2510345-1 |
|-------------|------------|
| Sample Date | 30-SEP-20 |
| Sample ID | BH20-5S |

| | | Guide | | |
|---------------------------------|------|-------|-----|--------|
| Analyte | Unit | #1 | #2 | |
| Benzene | ug/L | 10 | 2 | <0.50 |
| Chloroform | ug/L | 40 | 2 | <1.0 |
| 1,2-Dichlorobenzene | ug/L | 50 | 5.6 | <0.50 |
| 1,4-Dichlorobenzene | ug/L | 80 | 6.8 | <0.50 |
| cis-1,2-Dichloroethylene | ug/L | 4000 | 5.6 | <0.50 |
| Dichloromethane | ug/L | 2000 | 5.2 | <2.0 |
| trans-1,3-Dichloropropene | ug/L | 140 | - | <0.50 |
| Ethylbenzene | ug/L | 160 | 2 | <0.50 |
| 1,1,2,2-Tetrachloroethane | ug/L | 1400 | 17 | <0.50 |
| Tetrachloroethylene | ug/L | 1000 | 4.4 | <0.50 |
| Toluene | ug/L | 16 | 2 | <0.50 |
| Trichloroethylene | ug/L | 400 | 7.6 | < 0.50 |
| o-Xylene | ug/L | - | - | <0.50 |
| m+p-Xylenes | ug/L | - | - | <1.0 |
| Xylenes (Total) | ug/L | 1400 | 4.4 | <1.1 |
| Surrogate: 4-Bromofluorobenzene | % | - | - | 97.7 |
| Surrogate: 1,4-Difluorobenzene | % | - | - | 101.0 |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 11 of 17

09-OCT-20 12:10 (MT)

Polycyclic Aromatic Hydrocarbons - WATER

 Lab ID
 L2510345-1

 Sample Date
 30-SEP-20

 Sample ID
 BH20-5S

| | 11.24 | Guide | | |
|-----------------------------|-------|-------|----|--------|
| Analyte | Unit | #1 | #2 | |
| Acenaphthene | ug/L | - | - | 0.031 |
| Anthracene | ug/L | - | - | 0.048 |
| Benzo(a)anthracene | ug/L | - | - | 0.041 |
| Benzo(a)pyrene | ug/L | - | - | 0.020 |
| Benzo(b)fluoranthene | ug/L | - | - | 0.050 |
| Benzo(e)pyrene | ug/L | - | - | <0.050 |
| Benzo(ghi)perylene | ug/L | - | - | 0.027 |
| Benzo(k)fluoranthene | ug/L | - | - | 0.012 |
| Chrysene | ug/L | - | - | 0.048 |
| Dibenz(a,h)acridine | ug/L | - | - | <0.050 |
| Dibenz(a,j)acridine | ug/L | - | - | <0.050 |
| Dibenzo(a,h)anthracene | ug/L | - | - | <0.010 |
| Dibenzo(a,i)pyrene | ug/L | - | - | <0.050 |
| 7H-Dibenzo(c,g)carbazole | ug/L | - | - | <0.050 |
| 1,3-Dinitropyrene | ug/L | - | - | <1.0 |
| 1,6-Dinitropyrene | ug/L | - | - | <1.0 |
| 1,8-Dinitropyrene | ug/L | - | - | <1.0 |
| Fluoranthene | ug/L | - | - | 0.103 |
| Fluorene | ug/L | - | - | 0.013 |
| Indeno(1,2,3-cd)pyrene | ug/L | - | - | 0.024 |
| Naphthalene | ug/L | - | - | 0.028 |
| Perylene | ug/L | - | - | <0.010 |
| Phenanthrene | ug/L | - | - | 0.041 |
| Pyrene | ug/L | - | - | 0.172 |
| Surrogate: 2-Fluorobiphenyl | % | - | - | 88.1 |
| Surrogate: d14-Terphenyl | % | - | - | 88.3 |
| Surrogate: p-Terphenyl d14 | % | - | - | 106.9 |
| Total PAHs | ug/L | 5 | 2 | <1.7 |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 12 of 17

09-OCT-20 12:10 (MT)

Semi-Volatile Organics - WATER

| | Sampl | e Date | L2510345-1 30-SEP-20 |
|------|-----------------------------------|--|--|
| | San | ipie ID | BH20-5S |
| Unit | Guide #1 | Limits #2 | |
| ug/L | 2 | 0.8 | <0.40 |
| ug/L | 80 | 15 | <1.0 |
| ug/L | 12 | 8.8 | <2.0 |
| ug/L | 5 | 2 | <1.0 RRR |
| % | - | - | 92.8 |
| % | - | - | 87.2 |
| % | - | - | 107.1 |
| | ug/L ug/L ug/L ug/L % | Sample S | ug/L 2 0.8 ug/L 80 15 ug/L 12 8.8 ug/L 5 2 % % |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 13 of 17

09-OCT-20 12:10 (MT)

Polychlorinated Biphenyls - WATER

| . Ciyomormatoa Bipilonyio | **/ | | | |
|---------------------------------|------|-------------|--------------|------------|
| | | | Lab ID | L2510345-1 |
| | | Sampl | e Date | 30-SEP-20 |
| | | San | nple ID | BH20-5S |
| Analyte | Unit | Guide #1 | Limits #2 | |
| Aroclor 1242 | ug/L | - | - | <0.020 |
| Aroclor 1248 | ug/L | - | - | <0.020 |
| Aroclor 1254 | ug/L | - | - | <0.020 |
| Aroclor 1260 | ug/L | - | - | <0.020 |
| Surrogate: Decachlorobiphenyl | % | - | - | 119.5 |
| Total PCBs | ug/L | 1 | 0.4 | <0.040 |
| Surrogate: Tetrachloro-m-xylene | % | - | - | 93.1 |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.



L2510345 CONT'D....

Job Reference: G4842

PAGE 14 of 17

09-OCT-20 12:10 (MT)

Organic Parameters - WATER

| | | I | _ab ID | L2510345-1 |
|---------------------------------------|--------------|-------------|--------------|---------------|
| | | Sample | e Date | 30-SEP-20 |
| | | Sam | ple ID | BH20-5S |
| Analyte | Unit | Guide #1 | Limits #2 | |
| Analyte | | | | |
| | | | | |
| Nonylphenol | ug/L | 20 | 1 | <1.0 |
| Nonylphenol Nonylphenol Diethoxylates | ug/L ug/L | 20 | 1 - | <1.0 <0.10 |
| 71 | J | | · | |

Guide Limit #1: Ontario Toronto Sanitary Discharge Sewer By-Law Guide Limit #2: Ontario Toronto Storm Sewer By-Law

^{*} Please refer to the Reference Information section for an explanation of any qualifiers noted.

Reference Information

L2510345 CONT'D.... Job Reference: G4842 PAGE 15 of 17 09-OCT-20 12:10 (MT)

Additional Comments for Sample Listed:

| Samplenum | Matrix | Report Remarks | Sample Comments |
|------------|--------|--|-----------------|
| L2510345-1 | Water | Note: RRR: Detection limit raised due to suspected | |
| | | bias low results at or near the detection limit. | |

Qualifiers for Individual Parameters Listed: . . .:

| Qualifier | Description |
|-----------|---|
| DLDS | Detection Limit Raised: Dilution required due to high Dissolved Solids / Electrical Conductivity. |
| BODL | Limit of Reporting for BOD was increased to account for the largest volume of sample tested. |
| DLHC | Detection Limit Raised: Dilution required due to high concentration of test analyte(s). |
| RRR | Refer to Report Remarks for issues regarding this analysis |

Methods Listed (if applicable):

0 110

| | ALS Test Code | Matrix | Test Description | Method Reference** | |
|--|---------------|--------|------------------|--------------------|--|
|--|---------------|--------|------------------|--------------------|--|

625-PAH-LOW-WT Water EPA 8270 PAH (Low Level) SW846 8270

Aqueous samples are extracted and extracts are analyzed on GC/MSD. Depending on the analytical GC/MS column used benzo(i)fluoranthene may chromatographically co-elute with benzo(b)fluoranthene or benzo(k)fluoranthene.

625-SAN-WT Water Ontario Sanitary Sewer SVOC Target SW-846 8270

Samples are extracted with solvent and then analyzed by GC/MS.

BOD-WT Water BOD **APHA 5210 B**

This analysis is carried out using procedures adapted from APHA Method 5210B - "Biochemical Oxygen Demand (BOD)". All forms of biochemical oxygen demand (BOD) are determined by diluting and incubating a sample for a specified time period, and measuring the oxygen depletion using a dissolved oxygen meter. Dissolved BOD (SOLUBLE) is determined by filtering the sample through a glass fibre filter prior to dilution. Carbonaceous BOD (CBOD) is determined by adding a nitrification inhibitor to the diluted sample prior to incubation.

CN-TOT-WT Water Cyanide, Total ISO 14403-2

Total cyanide is determined by the combination of UV digestion and distillation. Cyanide is converted to cyanogen chloride by reacting with chloramine-T, the cyanogen chloride then reacts with a combination of barbituric acid and isonicotinic acid to form a highly colored complex.

When using this method, high levels of thiocyanate in samples can cause false positives at ~1-2% of the thiocyanate concentration. For samples with detectable cyanide analyzed by this method, ALS recommends analysis for thiocyanate to check for this potential interference

CR-CR6-IC-WT Water Chromium +6 FPA 7199

This analysis is carried out using procedures adapted from "Test Methods for Evaluating Solid Waste" SW-846, Method 7199, published by the United States Environmental Protection Agency (EPA). The procedure involves analysis for chromium (VI) by ion chromatography using diphenylcarbazide in a sulphuric acid solution. Chromium (III) is calculated as the difference between the total chromium and the chromium (VI) results.

Analysis conducted in accordance with the Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act (July 1, 2011).

EC-SCREEN-WT Water Conductivity Screen (Internal Use **APHA 2510**

Only)

Qualitative analysis of conductivity where required during preparation of other tests - e.g. TDS, metals, etc.

EC-WW-MF-WT Water F. Coli SM 9222D

A 100 mL volume of sample is filtered through a membrane, the membrane is placed on mFC-BCIG agar and incubated at 44.5 –0 .2 °C for 24 – 2 h. Method ID: WT-TM-1200

F-IC-N-WT Water Fluoride in Water by IC EPA 300.1 (mod)

Reference Information

L2510345 CONT'D....
Job Reference: G4842
PAGE 16 of 17
09-OCT-20 12:10 (MT)

Methods Listed (if applicable):

ALS Test Code Matrix Test Description Method Reference**

Inorganic anions are analyzed by Ion Chromatography with conductivity and/or UV detection.

HG-T-CVAA-WT Water Total Mercury in Water by CVAAS EPA 1631E (mod)

Water samples undergo a cold-oxidation using bromine monochloride prior to reduction with stannous chloride, and analyzed by CVAAS.

MET-T-CCMS-WT Water Total Metals in Water by CRC ICPMS EPA 200.2/6020A (mod)

Water samples are digested with nitric and hydrochloric acids, and analyzed by CRC ICPMS.

Method Limitation (re: Sulfur): Sulfide and volatile sulfur species may not be recovered by this method.

Analysis conducted in accordance with the Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act (July 1, 2011).

NP,NPE-LCMS-WT Water Nonylphenols and Ethoxylates by J. Chrom A849 (1999) p.467-482

LC/MS-MS

Water samples are filtered and analyzed on LCMS/MS by direct injection.

OGG-SPEC-CALC-WT Water Speciated Oil and Grease A/V Calc CALCULATION

Sample is extracted with hexane, sample speciation into mineral and animal/vegetable fractions is achieved via silica gel separation and is then determined gravimetrically.

OGG-SPEC-WT Water Speciated Oil and Grease-Gravimetric APHA 5520 B

The procedure involves an extraction of the entire water sample with hexane. Sample speciation into mineral and animal/vegetable fractions is achieved via silica gel separation and is then

determined gravimetrically.

P-T-COL-WT Water Total P in Water by Colour APHA 4500-P PHOSPHORUS

This analysis is carried out using procedures adapted from APHA Method 4500-P "Phosphorus". Total Phosphorus is deteremined colourimetrically after persulphate digestion of the sample.

PAH-EXTRA-WT Water Sanitary Sewer Use By-Law Additional SW 846 8270

PAH

PAH-SUM-CALC-WT Water TOTAL PAH's CALCULATION

Total PAH represents the sum of all PAH analytes reported for a given sample. Note that regulatory agencies and criteria differ in their definitions of Total PAH in terms of the individual PAH analytes

to be included.

PCB-WT Water Polychlorinated Biphenyls EPA 8082

PCBs are extracted from an aqueous sample at neutral pH with aliquots of dichloromethane using a modified separatory funnel technique. The extracts are analyzed by GC/MSD.

PH-WT Water pH APHA 4500 H-Electrode

Water samples are analyzed directly by a calibrated pH meter.

Analysis conducted in accordance with the Protocol for Analytical Methods Used in the Assessment of Properties under Part XV.1 of the Environmental Protection Act (July 1, 2011). Holdtime for

samples under this regulation is 28 days

PHENOLS-4AAP-WT Water Phenol (4AAP) EPA 9066

Reference Information

L2510345 CONT'D....
Job Reference: G4842
PAGE 17 of 17
09-OCT-20 12:10 (MT)

Methods Listed (if applicable):

ALS Test Code Matrix Test Description Method Reference**

An automated method is used to distill the sample. The distillate is then buffered to pH 9.4 which reacts with 4AAP and potassium ferricyanide to form a red complex which is measured

colorimetrically.

SOLIDS-TSS-WT Water Suspended solids APHA 2540 D-Gravimetric

A well-mixed sample is filtered through a weighed standard glass fibre filter and the residue retained is dried in an oven at 104–1°C for a minimum of four hours or until a constant weight is achieved.

TKN-F-WT Water TKN in Water by Fluorescence J. ENVIRON. MONIT., 2005,7,37-42,RSC

Total Kjeldahl Nitrogen is determined using block digestion followed by Flow-injection analysis with fluorescence detection

VOC-ROU-HS-WT Water Volatile Organic Compounds SW846 8260

Aqueous samples are analyzed by headspace-GC/MS.

XYLENES-SUM-CALC-WT Water Sum of Xylene Isomer Concentrations CALCULATION

Total xylenes represents the sum of o-xylene and m&p-xylene.

**ALS test methods may incorporate modifications from specified reference methods to improve performance.

Chain of Custody Numbers:

17-844660

The last two letters of the above test code(s) indicate the laboratory that performed analytical analysis for that test. Refer to the list below:

Laboratory Definition Code Laboratory Location

WT ALS ENVIRONMENTAL - WATERLOO, ONTARIO, CANADA

GLOSSARY OF REPORT TERMS

Surrogates are compounds that are similar in behaviour to target analyte(s), but that do not normally occur in environmental samples. For applicable tests, surrogates are added to samples prior to analysis as a check on recovery. In reports that display the D.L. column, laboratory objectives for surrogates are listed there.

ma/kg - milligrams per kilogram based on dry weight of sample

mg/kg wwt - milligrams per kilogram based on wet weight of sample

mg/kg lwt - milligrams per kilogram based on lipid-adjusted weight

mg/L - unit of concentration based on volume, parts per million.

< - Less than.

D.L. - The reporting limit.

N/A - Result not available. Refer to qualifier code and definition for explanation.

Test results reported relate only to the samples as received by the laboratory.

UNLESS OTHERWISE STATED, ALL SAMPLES WERE RECEIVED IN ACCEPTABLE CONDITION.

Analytical results in unsigned test reports with the DRAFT watermark are subject to change, pending final QC review.

Application of guidelines is provided "as is" without warranty of any kind, either expressed or implied, including, but not limited to, fitness for a particular purpose, or non-infringement. ALS assumes no responsibility for errors or omissions in the information. Guideline limits are not adjusted for the hardness, pH or temperature of the sample (the most conservative values are used). Measurement uncertainty is not applied to test results prior to comparison with specified criteria values.



Workorder: L2510345 Report Date: 09-OCT-20 Page 1 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|--------------------------|--------|-----------|--------|-----------|-------|-----|--------|-----------|
| 625-PAH-LOW-WT | Water | | | | | | | |
| Batch R5244941 | | | | | | | | |
| WG3416467-2 LCS | | | 00.5 | | 0/ | | | |
| Acenaphthene | | | 89.5 | | % | | 50-140 | 05-OCT-20 |
| Anthracene | | | 92.3 | | % | | 50-140 | 05-OCT-20 |
| Benzo(a)anthracene | | | 96.0 | | % | | 50-140 | 05-OCT-20 |
| Benzo(a)pyrene | | | 93.8 | | % | | 60-130 | 05-OCT-20 |
| Benzo(b)fluoranthene | | | 87.3 | | % | | 50-140 | 05-OCT-20 |
| Benzo(ghi)perylene | | | 94.7 | | % | | 50-140 | 05-OCT-20 |
| Benzo(k)fluoranthene | | | 100.0 | | % | | 50-140 | 05-OCT-20 |
| Chrysene | | | 106.4 | | % | | 50-140 | 05-OCT-20 |
| Dibenzo(a,h)anthracene | ! | | 97.7 | | % | | 50-140 | 05-OCT-20 |
| Fluoranthene | | | 95.7 | | % | | 50-140 | 05-OCT-20 |
| Fluorene | | | 92.0 | | % | | 50-140 | 05-OCT-20 |
| Indeno(1,2,3-cd)pyrene | | | 92.6 | | % | | 50-140 | 05-OCT-20 |
| Naphthalene | | | 94.5 | | % | | 50-130 | 05-OCT-20 |
| Perylene | | | 95.7 | | % | | 50-140 | 05-OCT-20 |
| Phenanthrene | | | 93.2 | | % | | 50-140 | 05-OCT-20 |
| Pyrene | | | 92.1 | | % | | 50-140 | 05-OCT-20 |
| WG3416467-1 MB | | | 0.040 | | | | 0.04 | |
| Acenaphthene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Anthracene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Benzo(a)anthracene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Benzo(a)pyrene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Benzo(b)fluoranthene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Benzo(ghi)perylene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Benzo(k)fluoranthene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Chrysene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Dibenzo(a,h)anthracene |) | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Fluoranthene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Fluorene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Indeno(1,2,3-cd)pyrene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Naphthalene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Perylene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Phenanthrene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Pyrene | | | <0.010 | | ug/L | | 0.01 | 05-OCT-20 |
| Surrogate: 2-Fluorobiphe | enyl | | 90.7 | | % | | 40-130 | 05-OCT-20 |
| | | | | | | | | |



Workorder: L2510345 Report Date: 09-OCT-20 Page 2 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|--|----------|-----------------------------|-------------------|-----------|-------|-----|--------|-----------|
| 625-PAH-LOW-WT | Water | | | | | | | |
| Batch R5244941 WG3416467-1 MB Surrogate: p-Terphenyl | | | 107.2 | | % | | 40-130 | 05-OCT-20 |
| 625-SAN-WT | Water | | | | | | | |
| Batch R5244183 | } | | | | | | | |
| WG3416467-2 LCS 3,3'-Dichlorobenzidine | | | 96.1 | | % | | 50-140 | 02-OCT-20 |
| Bis(2-ethylhexyl)phthala | ate | | 104.5 | | % | | 50-140 | 02-OCT-20 |
| Di-n-butylphthalate | | | 110.9 | | % | | 50-140 | 02-OCT-20 |
| Pentachlorophenol | | | 89.1 | | % | | 50-140 | 02-OCT-20 |
| WG3416467-1 MB 3,3'-Dichlorobenzidine | | | <0.40 | | ug/L | | 0.4 | 02-OCT-20 |
| Bis(2-ethylhexyl)phthala | ate | | <2.0 | | ug/L | | 2 | 02-OCT-20 |
| Di-n-butylphthalate | | | <1.0 | | ug/L | | 1 | 02-OCT-20 |
| Pentachlorophenol | | | <0.50 | | ug/L | | 0.5 | 02-OCT-20 |
| Surrogate: 2-Fluorobipl | nenyl | | 87.5 | | % | | 40-130 | 02-OCT-20 |
| Surrogate: 2,4,6-Tribro | mophenol | | 89.7 | | % | | 40-130 | 02-OCT-20 |
| Surrogate: p-Terphenyl | d14 | | 105.8 | | % | | 40-130 | 02-OCT-20 |
| BOD-WT | Water | | | | | | | |
| Batch R5248296 | • | | | | | | | |
| WG3416548-6 DUP BOD | | L2510109-8 <3.0 | <3.0 | RPD-NA | mg/L | N/A | 30 | 01-OCT-20 |
| WG3416548-7 LCS BOD | | | 96.0 | | % | | 85-115 | 01-OCT-20 |
| WG3416548-5 MB BOD | | | <2.0 | | mg/L | | 2 | 01-OCT-20 |
| CN-TOT-WT | Water | | | | | | | |
| Batch R5243865 | | | | | | | | |
| WG3416107-20 DUP Cyanide, Total | | WG3416107-1 < 0.0020 | 8 <0.0020 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| WG3416107-17 LCS Cyanide, Total | | | 111.4 | | % | | 80-120 | 01-OCT-20 |
| WG3416107-16 MB Cyanide, Total | | | <0.0020 | | mg/L | | 0.002 | 01-OCT-20 |
| WG3416107-19 MS Cyanide, Total | | WG3416107-1 | 8 115.9 | | % | | 70-130 | 01-OCT-20 |
| | | | | | | | | |



Workorder: L2510345 Report Date: 09-OCT-20 Page 3 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|---|--------|------------------------------|-----------|-----------|-----------|-----|----------|-----------|
| CR-CR6-IC-WT | Water | | | | | | | |
| Batch R5244057 WG3416355-4 DUP Chromium, Hexavalent | | WG3416355-3 <0.00050 | <0.00050 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| WG3416355-2 LCS Chromium, Hexavalent | | | 105.8 | | % | | 80-120 | 01-OCT-20 |
| WG3416355-1 MB Chromium, Hexavalent | | | <0.00050 | | mg/L | | 0.0005 | 01-OCT-20 |
| WG3416355-5 MS Chromium, Hexavalent | | WG3416355-3 | 104.9 | | % | | 70-130 | 01-OCT-20 |
| EC-WW-MF-WT | Water | | | | | | | |
| Batch R5243976 WG3416345-1 MB E. Coli | | | 0 | | CFU/100mL | | 1 | 01-OCT-20 |
| F-IC-N-WT | Water | | | | | | | |
| Batch R5244094 | | | | | | | | |
| WG3416485-10 DUP Fluoride (F) | | WG3416485-8 0.249 | 0.247 | | mg/L | 0.9 | 20 | 01-OCT-20 |
| WG3416485-7 LCS Fluoride (F) | | | 105.1 | | % | | 90-110 | 01-OCT-20 |
| WG3416485-6 MB Fluoride (F) | | | <0.020 | | mg/L | | 0.02 | 01-OCT-20 |
| WG3416485-9 MS Fluoride (F) | | WG3416485-8 | 97.6 | | % | | 75-125 | 01-OCT-20 |
| HG-T-CVAA-WT | Water | | | | | | | |
| Batch R5243372 WG3416177-4 DUP Mercury (Hg)-Total | | WG3416177-3 0.0000065 | 0.0000058 | | mg/L | 11 | 20 | 01-OCT-20 |
| WG3416177-2 LCS Mercury (Hg)-Total | | | 109.0 | | % | | 80-120 | 01-OCT-20 |
| WG3416177-1 MB Mercury (Hg)-Total | | | <0.000005 | C | mg/L | | 0.000005 | 01-OCT-20 |
| WG3416177-6 MS Mercury (Hg)-Total | | WG3416177-5 | 115.0 | | % | | 70-130 | 01-OCT-20 |
| MET-T-CCMS-WT | Water | | | | | | | |



Workorder: L2510345 Report Date: 09-OCT-20 Page 4 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|--|--------|-------------|-----------|-----------|-------|-----|--------|-----------|
| MET-T-CCMS-WT | Water | | | | | | | |
| Batch R5243465 | | | | | | | | |
| WG3415956-4 DUP | | WG3415956-3 | 0.0500 | | /1 | | | |
| Aluminum (Al)-Total | | 0.0562 | 0.0563 | DDD 114 | mg/L | 0.2 | 20 | 01-OCT-20 |
| Antimony (Sb)-Total | | <0.00010 | <0.00010 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| Arsenic (As)-Total | | 0.00029 | 0.00030 | | mg/L | 5.9 | 20 | 01-OCT-20 |
| Cadmium (Cd)-Total | | 0.0000050 | 0.0000052 | | mg/L | 3.9 | 20 | 01-OCT-20 |
| Chromium (Cr)-Total | | <0.00050 | <0.00050 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| Cobalt (Co)-Total | | <0.00010 | <0.00010 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| Copper (Cu)-Total | | 0.0452 | 0.0458 | | mg/L | 1.3 | 20 | 01-OCT-20 |
| Lead (Pb)-Total | | 0.000107 | 0.000109 | | mg/L | 2.0 | 20 | 01-OCT-20 |
| Manganese (Mn)-Total | | 0.00413 | 0.00426 | | mg/L | 3.2 | 20 | 01-OCT-20 |
| Molybdenum (Mo)-Total | | 0.000244 | 0.000269 | | mg/L | 9.7 | 20 | 01-OCT-20 |
| Nickel (Ni)-Total | | <0.00050 | <0.00050 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| Selenium (Se)-Total | | <0.000050 | <0.000050 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| Silver (Ag)-Total | | <0.000050 | <0.000050 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| Tin (Sn)-Total | | 0.00075 | 0.00085 | | mg/L | 12 | 20 | 01-OCT-20 |
| Titanium (Ti)-Total | | <0.00030 | <0.00030 | RPD-NA | mg/L | N/A | 20 | 01-OCT-20 |
| Zinc (Zn)-Total | | 0.0064 | 0.0062 | | mg/L | 3.5 | 20 | 01-OCT-20 |
| WG3415956-2 LCS Aluminum (Al)-Total | | | 102.5 | | % | | 80-120 | 01-OCT-20 |
| Antimony (Sb)-Total | | | 98.4 | | % | | 80-120 | 01-OCT-20 |
| Arsenic (As)-Total | | | 99.9 | | % | | 80-120 | 01-OCT-20 |
| Cadmium (Cd)-Total | | | 97.9 | | % | | 80-120 | 01-OCT-20 |
| Chromium (Cr)-Total | | | 100.4 | | % | | 80-120 | 01-OCT-20 |
| Cobalt (Co)-Total | | | 98.9 | | % | | 80-120 | 01-OCT-20 |
| Copper (Cu)-Total | | | 100.2 | | % | | 80-120 | 01-OCT-20 |
| Lead (Pb)-Total | | | 95.3 | | % | | 80-120 | 01-OCT-20 |
| Manganese (Mn)-Total | | | 101.4 | | % | | 80-120 | 01-OCT-20 |
| Molybdenum (Mo)-Total | | | 98.5 | | % | | 80-120 | 01-OCT-20 |
| Nickel (Ni)-Total | | | 99.0 | | % | | 80-120 | 01-OCT-20 |
| Selenium (Se)-Total | | | 98.8 | | % | | 80-120 | 01-OCT-20 |
| Silver (Ag)-Total | | | 99.4 | | % | | 80-120 | 01-OCT-20 |
| Tin (Sn)-Total | | | 93.9 | | % | | 80-120 | 01-OCT-20 |
| Titanium (Ti)-Total | | | 97.3 | | % | | 80-120 | 01-OCT-20 |
| Zinc (Zn)-Total | | | 97.5 | | % | | 80-120 | 01-OCT-20 |
| · · | | | | | | | - | - |



Workorder: L2510345 Report Date: 09-OCT-20 Page 5 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

Contact: Richard Sukhu

NP,NPE-LCMS-WT

Water

| Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|---------------------------------------|--------|-------------|--------------|-----------|-------|-----|-------------|------------------------|
| MET-T-CCMS-WT | Water | | | | | | | |
| Batch R5243465 | | | | | | | | |
| WG3415956-1 MB | | | | | 4 | | 2 225 | |
| Aluminum (Al)-Total | | | <0.0050 | | mg/L | | 0.005 | 01-OCT-20 |
| Antimony (Sb)-Total | | | <0.00010 | | mg/L | | 0.0001 | 01-OCT-20 |
| Arsenic (As)-Total | | | <0.00010 | _ | mg/L | | 0.0001 | 01-OCT-20 |
| Cadmium (Cd)-Total | | | <0.000005 | C | mg/L | | 0.000005 | 01-OCT-20 |
| Chromium (Cr)-Total | | | <0.00050 | | mg/L | | 0.0005 | 01-OCT-20 |
| Cobalt (Co)-Total | | | <0.00010 | | mg/L | | 0.0001 | 01-OCT-20 |
| Copper (Cu)-Total | | | <0.00050 | | mg/L | | 0.0005 | 01-OCT-20 |
| Lead (Pb)-Total | | | <0.000050 | | mg/L | | 0.00005 | 01-OCT-20 |
| Manganese (Mn)-Total | | | <0.00050 | | mg/L | | 0.0005 | 01-OCT-20 |
| Molybdenum (Mo)-Total | | | <0.000050 | | mg/L | | 0.00005 | 01-OCT-20 |
| Nickel (Ni)-Total | | | <0.00050 | | mg/L | | 0.0005 | 01-OCT-20 |
| Selenium (Se)-Total | | | <0.000050 | | mg/L | | 0.00005 | 01-OCT-20 |
| Silver (Ag)-Total | | | <0.000050 | | mg/L | | 0.00005 | 01-OCT-20 |
| Tin (Sn)-Total | | | <0.00010 | | mg/L | | 0.0001 | 01-OCT-20 |
| Titanium (Ti)-Total | | | <0.00030 | | mg/L | | 0.0003 | 01-OCT-20 |
| Zinc (Zn)-Total | | | <0.0030 | | mg/L | | 0.003 | 01-OCT-20 |
| WG3415956-5 MS Aluminum (Al)-Total | | WG3415956-3 | 97.7 | | % | | 70-130 | 01-OCT-20 |
| Antimony (Sb)-Total | | | 100.2 | | % | | 70-130 | 01-OCT-20 |
| Arsenic (As)-Total | | | 99.9 | | % | | 70-130 | 01-OCT-20 |
| Cadmium (Cd)-Total | | | 98.6 | | % | | 70-130 | 01-OCT-20 |
| Chromium (Cr)-Total | | | 102.1 | | % | | 70-130 | 01-OCT-20 |
| Cobalt (Co)-Total | | | 100.8 | | % | | 70-130 | 01-OCT-20 |
| Copper (Cu)-Total | | | N/A | MS-B | % | | - | 01-OCT-20 |
| Lead (Pb)-Total | | | 97.1 | WOD | % | | - 70-130 | 01-OCT-20 01-OCT-20 |
| Manganese (Mn)-Total | | | 101.0 | | % | | 70-130 | 01-OCT-20 |
| Molybdenum (Mo)-Total | | | 99.8 | | % | | 70-130 | 01-OCT-20 01-OCT-20 |
| Nickel (Ni)-Total | | | 99.2 | | % | | 70-130 | 01-OCT-20 01-OCT-20 |
| Selenium (Se)-Total | | | 99.9 | | % | | 70-130 | 01-OCT-20 01-OCT-20 |
| Silver (Ag)-Total | | | 97.9 | | % | | 70-130 | 01-OCT-20 01-OCT-20 |
| Tin (Sn)-Total | | | 95.3 | | % | | 70-130 | 01-OCT-20 01-OCT-20 |
| Titanium (Ti)-Total | | | 95.3 95.3 | | % | | | |
| Zinc (Zn)-Total | | | 97.6 | | % | | 70-130 | 01-OCT-20 |
| Zino (Zin) Total | | | 37.0 | | 70 | | 70-130 | 01-OCT-20 |



Workorder: L2510345 Report Date: 09-OCT-20 Page 6 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|--------------------------------------|--------|------------|---------|-----------|-------|-----|--------|-----------|
| NP,NPE-LCMS-WT | Water | | | | | | | |
| Batch R5244080 | | | | | | | | |
| WG3416911-3 DUP | | L2510715-1 | | | | | | |
| Nonylphenol | | <1.0 | <1.0 | RPD-NA | ug/L | N/A | 30 | 02-OCT-20 |
| Nonylphenol Monoethox | | <2.0 | <2.0 | RPD-NA | ug/L | N/A | 30 | 02-OCT-20 |
| Nonylphenol Diethoxylat | es | <0.10 | <0.10 | RPD-NA | ug/L | N/A | 30 | 02-OCT-20 |
| WG3416911-2 LCS Nonylphenol | | | 86.6 | | % | | 75-125 | 02-OCT-20 |
| Nonylphenol Monoethox | ylates | | 102.5 | | % | | 75-125 | 02-OCT-20 |
| Nonylphenol Diethoxylat | es | | 105.0 | | % | | 75-125 | 02-OCT-20 |
| WG3416911-1 MB Nonylphenol | | | <1.0 | | ug/L | | 1 | 02-OCT-20 |
| Nonylphenol Monoethox | ylates | | <2.0 | | ug/L | | 2 | 02-OCT-20 |
| Nonylphenol Diethoxylat | | | <0.10 | | ug/L | | 0.1 | 02-OCT-20 |
| WG3416911-4 MS | | L2510715-1 | | | - | | | |
| Nonylphenol | | | 102.0 | | % | | 50-150 | 02-OCT-20 |
| Nonylphenol Monoethox | ylates | | 120.9 | | % | | 50-150 | 02-OCT-20 |
| Nonylphenol Diethoxylat | es | | 100.2 | | % | | 50-150 | 02-OCT-20 |
| OGG-SPEC-WT | Water | | | | | | | |
| Batch R5243130 | | | | | | | | |
| WG3415929-2 LCS | | | 00.5 | | 0/ | | | |
| Oil and Grease, Total | | | 92.5 | | % | | 70-130 | 01-OCT-20 |
| Mineral Oil and Grease | | | 81.9 | | % | | 70-130 | 01-OCT-20 |
| WG3415929-1 MB Oil and Grease, Total | | | <5.0 | | mg/L | | 5 | 01-OCT-20 |
| Mineral Oil and Grease | | | <2.5 | | mg/L | | 2.5 | 01-OCT-20 |
| P-T-COL-WT | Water | | | | J | | | 0. 00. 20 |
| Batch R5245145 | | | | | | | | |
| WG3415971-3 DUP | | L2510411-7 | | | | | | |
| Phosphorus, Total | | 0.0506 | 0.0471 | | mg/L | 7.2 | 20 | 05-OCT-20 |
| WG3415971-2 LCS Phosphorus, Total | | | 97.9 | | % | | 80-120 | 05-OCT-20 |
| WG3415971-1 MB Phosphorus, Total | | | <0.0030 | | mg/L | | 0.003 | 05-OCT-20 |
| WG3415971-4 MS Phosphorus, Total | | L2510411-7 | 85.8 | | % | | 70-130 | 05-OCT-20 |
| PAH-EXTRA-WT | Water | | | | | | | |



Qualifier

Workorder: L2510345 Report Date: 09-OCT-20 Page 7 of 11

RPD

Limit

Analyzed

Units

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

Matrix

Water

Reference

Result

VAUGHAN ON L4H 3H9

Contact: Richard Sukhu

Test

PAH-EXTRA-WT

| Batch R5244452 WG3416467-2 LCS | | | | |
|--|-----------------------------------|-----------------------------------|----------------------------|-----------|
| Benzo(e)pyrene | 112.3 | % | 60-130 | 03-OCT-20 |
| 1,3-Dinitropyrene | 133.9 L | .CS-H % | 60-130 | 03-OCT-20 |
| 1,6-Dinitropyrene | 157.8 F | RRQC % | 60-130 | 03-OCT-20 |
| Dibenz(a,h)acridine | 107.9 | % | 60-130 | 03-OCT-20 |
| 1,8-Dinitropyrene | 163.5 F | RRQC % | 60-130 | 03-OCT-20 |
| Dibenz(a,j)acridine | 112.4 | % | 60-130 | 03-OCT-20 |
| 7H-Dibenzo(c,g)carbazole | 112.5 | % | 60-130 | 03-OCT-20 |
| Dibenzo(a,i)pyrene | 82.2 | % | 60-130 | 03-OCT-20 |
| COMMENTS: RRQC; Result is outside A WG3416467-1 MB | | | | |
| Benzo(e)pyrene | <0.050 | ug/L | 0.05 | 03-OCT-20 |
| 1,3-Dinitropyrene | <1.0 | ug/L | 1 | 03-OCT-20 |
| 1,6-Dinitropyrene | <1.0 | ug/L | 1 | 03-OCT-20 |
| Dibenz(a,h)acridine | <0.050 | ug/L | 0.05 | 03-OCT-20 |
| 1,8-Dinitropyrene | | RRQC ug/L | 1 | 03-OCT-20 |
| Dibenz(a,j)acridine | <0.050 | ug/L | 0.05 | 03-OCT-20 |
| 7H-Dibenzo(c,g)carbazole | <0.050 | ug/L | 0.05 | 03-OCT-20 |
| Dibenzo(a,i)pyrene | <0.050 | ug/L | 0.05 | 03-OCT-20 |
| Surrogate: d14-Terphenyl | 88.4 | % | 40-130 | 03-OCT-20 |
| COMMENTS: RRQC; Result is outside A | ALS control limits due to instrum | ent background. The reporting lin | nit has been raised accord | lingly |
| PCB-WT Water | | | | |
| Batch R5246318 | | | | |
| WG3416062-2 LCS Aroclor 1242 | 106.9 | % | 65-130 | 05-OCT-20 |
| Aroclor 1248 | 83.9 | % | 65-130 | 05-OCT-20 |
| Aroclor 1254 | 106.9 | % | 65-130 | 05-OCT-20 |
| Aroclor 1260 | 110.8 | % | 65-130 | 05-OCT-20 |
| WG3416062-1 MB | | | | |
| Aroclor 1242 | <0.020 | ug/L | 0.02 | 05-OCT-20 |
| Aroclor 1248 | <0.020 | ug/L | 0.02 | 05-OCT-20 |
| Aroclor 1254 | <0.020 | ug/L | 0.02 | 05-OCT-20 |
| Aroclor 1260 | <0.020 | ug/L | 0.02 | 05-OCT-20 |
| Surrogate: Decachlorobiphenyl | 117.3 | % | 50-150 | 05-OCT-20 |
| Surrogate: Tetrachloro-m-xylene | 82.4 | % | 50-150 | 05-OCT-20 |
| Water | | | | |



Workorder: L2510345 Report Date: 09-OCT-20 Page 8 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|---|--------|----------------------------|---------|-----------|----------|------|---------|-----------|
| PH-WT | Water | | | | | | | |
| Batch R5243111 WG3416100-4 DUP pH | | WG3416100-3 8.10 | 8.02 | J | pH units | 0.08 | 0.2 | 01-OCT-20 |
| WG3416100-2 LCS pH | | | 7.02 | | pH units | | 6.9-7.1 | 01-OCT-20 |
| PHENOLS-4AAP-WT | Water | | | | | | | |
| Batch R5244059 WG3415972-3 DUP Phenols (4AAP) | | WG3415972-5 0.0056 | 0.0058 | | mg/L | 2.5 | 20 | 01-OCT-20 |
| WG3415972-2 LCS Phenols (4AAP) | | | 99.6 | | % | | 85-115 | 01-OCT-20 |
| WG3415972-1 MB Phenols (4AAP) | | | <0.0010 | | mg/L | | 0.001 | 01-OCT-20 |
| WG3415972-4 MS Phenols (4AAP) | | WG3415972-5 | 104.3 | | % | | 75-125 | 01-OCT-20 |
| SOLIDS-TSS-WT | Water | | | | | | | |
| Batch R5247460 WG3417646-3 DUP Total Suspended Solids | | L2510088-1 5.4 | 4.6 | | mg/L | 16 | 20 | 06-OCT-20 |
| WG3417646-2 LCS Total Suspended Solids | | | 97.0 | | % | .0 | 85-115 | 06-OCT-20 |
| WG3417646-1 MB Total Suspended Solids | | | <3.0 | | mg/L | | 3 | 06-OCT-20 |
| TKN-F-WT | Water | | | | | | | |
| Batch R5244077 WG3415970-3 DUP | | L2510487-5 | 0.40 | | | | | |
| Total Kjeldahl Nitrogen | | 3.15 | 3.13 | | mg/L | 0.6 | 20 | 01-OCT-20 |
| WG3415970-2 LCS Total Kjeldahl Nitrogen | | | 109.3 | | % | | 75-125 | 01-OCT-20 |
| WG3415970-1 MB Total Kjeldahl Nitrogen | | | <0.050 | | mg/L | | 0.05 | 01-OCT-20 |
| WG3415970-4 MS Total Kjeldahl Nitrogen | | L2510487-5 | 105.6 | | % | | 70-130 | 01-OCT-20 |
| VOC-ROU-HS-WT | Water | | | | | | | |
| Batch R5243096 WG3415903-4 DUP 1,1,2,2-Tetrachloroethan | ne | WG3415903-3 <0.50 | <0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| 1,2-Dichlorobenzene | | <0.50 | <0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |



Workorder: L2510345 Report Date: 09-OCT-20 Page 9 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test Ma | atrix Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|---------------------------|-----------------|--------|-----------|-------|-----|--------|-----------|
| VOC-ROU-HS-WT W | ater | | | | | | |
| Batch R5243096 | | | | | | | |
| WG3415903-4 DUP | WG3415903- | - | | | | | |
| 1,4-Dichlorobenzene | <0.50 | <0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| Benzene | <0.50 | <0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| Chloroform | <1.0 | <1.0 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| cis-1,2-Dichloroethylene | <0.50 | < 0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| Dichloromethane | <2.0 | <2.0 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| Ethylbenzene | <0.50 | <0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| m+p-Xylenes | <1.0 | < 0.40 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| o-Xylene | <0.50 | < 0.30 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| Tetrachloroethylene | <0.50 | <0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| Toluene | <0.50 | <0.40 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| trans-1,3-Dichloropropene | <0.50 | < 0.30 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| Trichloroethylene | <0.50 | <0.50 | RPD-NA | ug/L | N/A | 30 | 01-OCT-20 |
| WG3415903-1 LCS | | | | | | | |
| 1,1,2,2-Tetrachloroethane | | 61.0 | MES | % | | 70-130 | 01-OCT-20 |
| 1,2-Dichlorobenzene | | 97.8 | | % | | 70-130 | 01-OCT-20 |
| 1,4-Dichlorobenzene | | 100.5 | | % | | 70-130 | 01-OCT-20 |
| Benzene | | 100.1 | | % | | 70-130 | 01-OCT-20 |
| Chloroform | | 101.6 | | % | | 70-130 | 01-OCT-20 |
| cis-1,2-Dichloroethylene | | 94.6 | | % | | 70-130 | 01-OCT-20 |
| Dichloromethane | | 96.1 | | % | | 70-130 | 01-OCT-20 |
| Ethylbenzene | | 96.6 | | % | | 70-130 | 01-OCT-20 |
| m+p-Xylenes | | 97.3 | | % | | 70-130 | 01-OCT-20 |
| o-Xylene | | 102.8 | | % | | 70-130 | 01-OCT-20 |
| Tetrachloroethylene | | 97.1 | | % | | 70-130 | 01-OCT-20 |
| Toluene | | 97.4 | | % | | 70-130 | 01-OCT-20 |
| trans-1,3-Dichloropropene | | 93.2 | | % | | 70-130 | 01-OCT-20 |
| Trichloroethylene | | 102.3 | | % | | 70-130 | 01-OCT-20 |
| WG3415903-2 MB | | | | | | | |
| 1,1,2,2-Tetrachloroethane | | <0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| 1,2-Dichlorobenzene | | <0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| 1,4-Dichlorobenzene | | < 0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| Benzene | | < 0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| Chloroform | | <1.0 | | ug/L | | 1 | 01-OCT-20 |
| cis-1,2-Dichloroethylene | | <0.50 | | | | 0.5 | |



Workorder: L2510345 Report Date: 09-OCT-20 Page 10 of 11

Client: MCCLYMONT & RAK ENG. INC

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

| Test Test | Matrix | Reference | Result | Qualifier | Units | RPD | Limit | Analyzed |
|---------------------------------|--------|-----------|--------|-----------|-------|-----|--------|-----------|
| VOC-ROU-HS-WT | Water | | | | | | | |
| Batch R5243096 | | | | | | | | |
| WG3415903-2 MB | | | | | | | | |
| cis-1,2-Dichloroethylene |) | | <0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| Dichloromethane | | | <2.0 | | ug/L | | 2 | 01-OCT-20 |
| Ethylbenzene | | | < 0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| m+p-Xylenes | | | <0.40 | | ug/L | | 0.4 | 01-OCT-20 |
| o-Xylene | | | < 0.30 | | ug/L | | 0.3 | 01-OCT-20 |
| Tetrachloroethylene | | | < 0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| Toluene | | | < 0.40 | | ug/L | | 0.4 | 01-OCT-20 |
| trans-1,3-Dichloroprope | ne | | < 0.30 | | ug/L | | 0.3 | 01-OCT-20 |
| Trichloroethylene | | | <0.50 | | ug/L | | 0.5 | 01-OCT-20 |
| Surrogate: 1,4-Difluorobenzene | | | 101.9 | | % | | 70-130 | 01-OCT-20 |
| Surrogate: 4-Bromofluorobenzene | | | 96.6 | | % | | 70-130 | 01-OCT-20 |
| WG3415903-5 MS | | WG3415903 | | | | | | |
| 1,1,2,2-Tetrachloroetha | ne | | 76.3 | | % | | 50-150 | 01-OCT-20 |
| 1,2-Dichlorobenzene | | | 96.7 | | % | | 50-150 | 01-OCT-20 |
| 1,4-Dichlorobenzene | | | 95.1 | | % | | 50-150 | 01-OCT-20 |
| Benzene | | | 100.5 | | % | | 50-150 | 01-OCT-20 |
| Chloroform | | | 104.0 | | % | | 50-150 | 01-OCT-20 |
| cis-1,2-Dichloroethylene |) | | 97.7 | | % | | 50-150 | 01-OCT-20 |
| Dichloromethane | | | 101.5 | | % | | 50-150 | 01-OCT-20 |
| Ethylbenzene | | | 90.9 | | % | | 50-150 | 01-OCT-20 |
| m+p-Xylenes | | | 91.3 | | % | | 50-150 | 01-OCT-20 |
| o-Xylene | | | 99.0 | | % | | 50-150 | 01-OCT-20 |
| Tetrachloroethylene | | | 88.2 | | % | | 50-150 | 01-OCT-20 |
| Toluene | | | 93.3 | | % | | 50-150 | 01-OCT-20 |
| trans-1,3-Dichloroprope | ne | | 95.1 | | % | | 50-150 | 01-OCT-20 |
| Trichloroethylene | | | 98.3 | | % | | 50-150 | 01-OCT-20 |

Report Date: 09-OCT-20 Workorder: L2510345

MCCLYMONT & RAK ENG. INC Client: Page 11 of 11

111 ZENWAY BLVD. UNIT 4

VAUGHAN ON L4H 3H9

Contact: Richard Sukhu

Legend:

ALS Control Limit (Data Quality Objectives)

DUP Duplicate

RPD Relative Percent Difference

N/A Not Available

LCS Laboratory Control Sample SRM Standard Reference Material

MS Matrix Spike

Matrix Spike Duplicate **MSD**

Average Desorption Efficiency ADE

Method Blank MB

Internal Reference Material IRM CRM Certified Reference Material Continuing Calibration Verification CCV CVS Calibration Verification Standard LCSD Laboratory Control Sample Duplicate

Sample Parameter Qualifier Definitions:

| Qualifier | Description |
|-----------|---|
| J | Duplicate results and limits are expressed in terms of absolute difference. |
| LCS-H | Lab Control Sample recovery was above ALS DQO. Non-detected sample results are considered reliable. Other results, if reported, have been qualified. |
| MES | Data Quality Objective was marginally exceeded (by < 10% absolute) for < 10% of analytes in a Multi-Element Scan / Multi-Parameter Scan (considered acceptable as per OMOE & CCME). |
| MS-B | Matrix Spike recovery could not be accurately calculated due to high analyte background in sample. |
| RPD-NA | Relative Percent Difference Not Available due to result(s) being less than detection limit. |
| RRQC | Refer to report remarks for information regarding this QC result. |

Hold Time Exceedances:

All test results reported with this submission were conducted within ALS recommended hold times.

ALS recommended hold times may vary by province. They are assigned to meet known provincial and/or federal government requirements. In the absence of regulatory hold times, ALS establishes recommendations based on guidelines published by the US EPA, APHA Standard Methods, or Environment Canada (where available). For more information, please contact ALS.

The ALS Quality Control Report is provided to ALS clients upon request. ALS includes comprehensive QC checks with every analysis to ensure our high standards of quality are met. Each QC result has a known or expected target value, which is compared against predetermined data quality objectives to provide confidence in the accuracy of associated test results.

Please note that this report may contain QC results from anonymous Sample Duplicates and Matrix Spikes that do not originate from this Work Order.



Chain of Custody (COC) / Analytical Request Form


Canada Toll Free: 1 800 668 9878

L2510345-COFC

coc Number: 17 - 844660



| | www.aisglobal.com | | | | | | | | | | | | | | | |
|--|--|-----------------------------|--------------------------------|--|-----------------|---------------|--|--|----------------|--|-------------|-----------------|--------------|--|----------------|---------------------|
| Report To | Contact and company name below will appear on the final report | | Report Form | | | | | | | | _ | | | | may apply) | — |
| Company: | MCCLYMONT & PAK | Select Report For | <i>p</i> > (| | | | Regular [R] | | ard TAT If | | | | - no surchar | ges apply | | |
| Contact: | RICHARD SUKHU | | C) Report with Rep | P | | 1681 | day (P4-20%) | _ | SE SE | | ess day | | - | | | 니 |
| Phone: | 675-0160 | | its to Criteria on Report - | | | | day (P3-25%) | Ļ | | Same Da | y, Week | end or S | Statutory | holiday (E shr) 1 | 2 -200% | |
| | Company address below will appear on the final report | Select Distribution | | MAIL | | | day [P2-50%] | <u> </u> | | (rapora) | ory oper | | s may ap | | | _= |
| Street: | ZENWAY | Email 1 or Fax | rsukhu | e wich ra | K.com | | to and Time Req | | | | | | | yy hh:mm | | |
| City/Province: | VAUGHAN | Email 2 | | | | For teats the | rt can not be perfor | med according | to the sen | | | | icted. | | | |
| Postal Code: | | Email 3 | | | | <u> </u> | | | | | sis Requ | | | | | ┯┥ |
| Invaice To | Same as Report To X YES [] NO | | Invoice Dis | stribution | | ــا ﻣﯩﻠ | India | ale Filtered (I |), Preserv | red (P) or Fr | tered and P | reserved (| (F/P) below | | ↓ □ | |
| - | Copy of Invoice with Report YES NO | Select Invoice Di | stribution: 🔀 E | MATL MATL | FAX | | | | | | | | 무무 | \frac{4}{2} | | |
| Company. | | Email 1 or Fax | | | |] 🖫 🗀 | | | T | | | | | | ♀ | Įğ |
| Contact: | | Email 2 | | | | ≨ | | | | | |] | | i | | <u>=</u> |
| | Project Information | | | Oil and Gas Required Fields (client use) | | | ₹ 1 | | | | | | | | N N | å Çi |
| ALS Account# | / Quote #: | AFE/Cost Cemer: | | PO# | | CONTAINERS | ₿் ம | | | | } | | | [] | 10 | 🕏 |
| Job#: 64842 | | Major/Minor Code: | Major/Mnor Code: Routing Code: | | | | STORM PRY DDC | ! | | 1 | | | | 1 | S | <u>\$</u> |
| PO/AFE: | | Requisitioner: | Requisitioner | | | 씽 | 1 54 6 | | | | | | | | LЩ | SUSPECTED HAZARD (s |
| LSO: | | Location: | Location: | | | | 19 A | | | | | | | | ~ | 3 |
| - 5 to 1 to | 10510015 | PACS Contact: | | Sampler: | | 🗓 | 5.₹3 | | | | | | | | AMPI | 1 8 |
| ALS Lab Wo | ge Order # (leb use only): | The Contact: | | Sampler. | |] (29 | 100 SECUL | | | | | | | [| 3 | [5 |
| ALS Sample # | Sample Identification and/or Coordinate | 18 | Date | Time | Sample Type | NUMBER | 230 | | | | | | | | S | 100 |
| (leb use only) | (This description will appear on the report | i) | (dd-mmm-yy) | (hh:mm) | ontiple type | +=+ | F4 " | | 4_ | | _ | | | | 1.07 | ಹ |
| | BH 20-5S | | SEP. 30 | 9am | GW | 20 | X_{-} | | | | | | | <u> </u> | | |
| | 13(1-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0-0 | | | | <u> </u> | | | | \top | | | | | | i | |
| 1000 | | | <u> </u> | † | | 1 1 | 1 1 | 1 | | | \top | П | T | , | | |
| | <u> </u> | | - | | i - | + | + | | \top | \vdash | | \Box | | 1 | | |
| <u> </u> | | | | | | + | | ╁╌╁╴ | + | + + | | | | 1 ! | - | 1 |
| ٠. | | | | <u> </u> | | - | | + +- | | 1 | | \vdash | _ | ┿┈┼ | | |
| L | | | | <u> </u> | | ↓ _↓ | | $\downarrow \downarrow \downarrow$ | | 1— | | \vdash | _ | ├┈╼ ├┈ | - | |
| | ! | | | <u> </u> | | | | | | | | L | | | | - |
| <u> </u> | <u> </u> | | | | I | | | | | | | | | <u> </u> | | 丄 |
| | | | | | | | | | | 1 | | | | | l | |
| | | | | | | + + | - | 1 1 | | - | _ | | | | T | T . |
| | <u> </u> | | | | | | ++- | ┧╼╂╌ | _ | + | + | 1 | | † | | \top |
| | | . <u>.</u> | <u> </u> | | | + | ++ | | | + | | { -} | + | ╁╼┽╌ | +- | + |
| 75 . | | | l <u>.</u> | 1 | <u> </u> | \bot | | <u> </u> | | 1 | 10 050 | ENJEC I | lah uas a | | | |
| Deighi | ng Water (DW) Samples¹ (client use) | tions / Specify Criteria to | add on report by cik | king on the drap-d | lown list below | <u></u> | | | _ | NDITION Observati | | Yes Yes | lab use o | nay) N | | |
| | - · · · · · · · · · · · · · · · · · · · | (916) | etronic COC only) | | | Frozen | | · - | | | | Yes | ä | N | - | H |
| | en from a Regulated DW System? | | | | | | cs\ ☐ tce Initiated 🚡 | Cubes [| | IOO Y BOOK | maca | 103 | | | • | _ |
| | YES MO | | | | | COURT! | WALLY COC | | ATIOES | éc | | | FINAL COOL | ER TEMPER | NTURES °C | -,- |
| | human consumption/ use? | | | | | 12. | <u> </u> | | | · · · · · | | 7. / | | 7 | 1 | _ |
| 11 | YES NO | | Interes a Actualism | | ab (144° - 44) | 114- | 7 | <u> </u> | EIN | N QUICA | IENT OF | CEPTIO | N (lab us | e onka | | |
| Delegan | SHIPMENT RELEASE (client use) Date: / Ti | ime: Received by: | INSTRAL SHIPME | TRECEPTION (I | an use only) | Tane. | Received | by: | - 181 | 7) [| MIP | | 7 / | | Time! | 7 * 7 |
| Released by: | MCR SEP. 30/20 | Karan | hartal | | ة (ره ي | Time: | 4 | • | A1 | r | 3 D | Ψ. | LU |) | 1/2 | <u>'`T</u> |
| L | COLOR FOR ALCHOCATIONS AND CAMPILIANS INFORMATION | II AWA AWI | A ARCOVAN | DE LABORATORY | | W - CLIEN | TCOPY | | / H | | | · | | | • , | P-14E 5018 1MDH |





48 Dawson Road., Guelph, ON N1H 5V1 tel. (519) 763-0700 fax (519) 763-6684

November 23, 2020

Pier 27 Toronto (Northeast) Inc. 56 The Esplanade Suite 308 Toronto, ON M5E 1A7

Attention: Kristine Zwicker

Re: Single Well Response Test

Pier 27, Phase 3 Toronto, Ontario

Dear Kristine,

Please find below a summary of the insitu single well response test completed at 15 Queens Quay, Toronto. The purpose of the testing was to determine hydraulic conductivity of the soils at the 50 mm wells installed by McClymont and Rak Engineers Inc. as part of the geohydrology investigation. The borehole logs indicate that the wells were screened in fill.

INTRODUCTION

The field work took place on October 13, 2020. A stabilized water level was obtained using an electronic water level tape before testing began. Next, an electronic pressure transducer was installed in the well to measure pressure changes during the single well response test. A volume of water was removed from the well and water levels were measured as the water level recovered.

DATA ANALYSIS

The rising head test in BH 20-6-I was assessed using the Hvorslev equation to estimate hydraulic conductivity. The hydraulic conductivity of this unit has been estimated to be 1.4×10^{-6} m/sec. The data from BH 20-6-S was insufficient for analysis due to the speed of recharge, and we cannot provide a hydraulic conductivity for this unit.

QUALIFICATIONS

Insitu Contractors Inc. is licensed by both the Professional Engineers of Ontario to provide engineering services and by the Ministry of the Environment & Climate Change as a water well contractor. Our staff includes water well technicians and engineers who have accumulated over forty years' experience in soil and ground water and excavation projects.

This report has been prepared for Forward Engineering & Associates Inc. Its use by a third party, or decisions made based on it, are the sole responsibility of such parties. If you have any questions or concerns, please contact us at (519) 763-0700.

Sincerely,


Susanna Meteer, B.A., Dipl. Encl. SWRT data and graph

Harry Oussoren, P.Eng.


Slug Test - Hvorslev Method

homogeneous, isotropic, infinte medium

well radius = r



| time | depth to wl | H-h ₊ | $(H-h_t)/(H-H_o)$ |
|-------|-------------|-------|-------------------|
| (sec) | (m) | (m) | |
| 0 | 3.84 | 0.000 | 0.000 |
| 0 | 4.335 | 0.495 | 1.000 |
| 5 | 4.18 | 0.340 | 0.687 |
| 35 | 4.15 | 0.310 | 0.626 |
| 60 | 4.14 | 0.300 | 0.606 |
| 88 | 4.13 | 0.290 | 0.586 |
| 150 | 4.11 | 0.270 | 0.545 |
| 197 | 4.1 | 0.260 | 0.525 |
| 246 | 4.09 | 0.250 | 0.505 |
| 277 | 4.08 | 0.240 | 0.485 |
| 344 | 4.07 | 0.230 | 0.465 |
| 405 | 4.06 | 0.220 | 0.444 |
| 469 | 4.05 | 0.210 | 0.424 |
| 520 | 4.04 | 0.200 | 0.404 |
| 596 | 4.03 | 0.190 | 0.384 |
| 667 | 4.02 | 0.180 | 0.364 |
| 772 | 4.01 | 0.170 | 0.343 |
| 861 | 4 | 0.160 | 0.323 |
| 987 | 3.99 | 0.150 | 0.303 |
| 1097 | 3.98 | 0.140 | 0.283 |
| 1214 | 3.97 | 0.130 | 0.263 |
| 1320 | 3.96 | 0.120 | 0.242 |
| 1468 | 3.95 | 0.110 | 0.222 |
| 1660 | 3.94 | 0.100 | 0.202 |
| 1797 | 3.93 | 0.090 | 0.182 |
| 2043 | 3.92 | 0.080 | 0.162 |



 $k = r^2 \ln (L/R)$ 2 L T_o Calculated Value of k (m/sec)

< 1.4E-06 (m/sec)

r = 0.0254 m0.73 m

R= 0.1 m

To = 630 seconds

H = 0.73 m

 $H-H_0 = 0.235 \text{ m}$

1 L of water removed from 2-inch diameter well equals 0.495-m

Project Pier 27

Well #

BH20-6-I


Date

2020/10/13


Slug Test - Hvorslev Method

homogeneous, isotropic, infinte medium

well radius = r



| time | depth to wl | H-h t | $(H-h_t)/(H-H_o)$ |
|-------|-------------|--------|-------------------|
| (sec) | (m) | (m) | |
| 0 | 3.62 | -0.060 | -0.012 |
| 0 | 4.115 | 0.435 | 1.000 |
| 10 | 3.79 | 0.110 | 0.253 |
| 24 | 3.78 | 0.100 | 0.230 |
| 60 | 3.77 | 0.090 | 0.207 |
| 110 | 3.76 | 0.080 | 0.184 |
| 356 | 3.75 | 0.070 | 0.161 |



$$k = \frac{r^2 \ln (L/R)}{2 L T_o}$$
Calculated Value of k (m/sec)

 $\begin{array}{rcl} r = & 0.0254 \text{ m} \\ L = & 3 \text{ m} \\ R = & 0.1 \text{ m} \\ To = & \text{seconds} \end{array}$

H = 5.46 m

 $H-H_0 = 4.965 \text{ m}$

1 L of water removed from 2-inch diameter well equals 0.495-m

< too large to determine by slug test

 Project
 Pier 27
 Well #
 BH20-6-S
 Date
 2020/10/13