CONTAINERIZED SYSTEMS

Factory Built and Tested Mobile Packaged Plants



- · Fully customizable to meet various applications
- All equipment is pre-Installed and tested
- Can be used for Leg-Supported Silo or Bulk Bag Frame delivery system
- Requires minimal site preparations
- Mobile Capabilities
- Ideal for remote locations with basic services
- · Fully operational within 48 hours

OPTIONS:

- Heat
- Air Conditioning
- Electrical Outlets
- . Lighting Control Panel



A company driven to deliver the very best Polymer Blending, Chemical Feed, and Bulk Solids Handling Systems, fueled by constantly asking, "What If?"



CONTAINERIZED SYSTEMS

Factory Built and Tested Mobile Packaged Plants

FEATURES

Each containerized system is engineered to your specifications with multiple options available. These systems can include:

- Leg Supported Silo
- Bulk Bag Frame designed for 2-ton super sacks
- Storage hopper
- · Volumetric screw feeder
- Wetting cone or Slurry make down/storage tank with mixer, and level devices
- Slurry feed pumps, if required
- · All required piping and valves
- Local control system with programmable logic controller (PLC) including pre-programmed system logic. All systems are completely tested with water for engineer or customer viewing before leaving our facility. UL, CUL, and CSA control panel Certifications available.
- Systems are provided with all piping and conduit pre-assembled

VELODYNE ADVANTAGES

- Factory testing on all of our systems.
 These tests include:
 - Pressure testing all pipes and valves
 - Hydrostatic testing of our mix tanks
 - Complete sequencing of all devices, including motors and solenoids
 - All inspected by a VeloDyne quality assurance inspector
- VeloDyne provides the most complete containerized systems on the market, ultimately saving time for the contractor and eliminating frustrating installation issues.
- VeloDyne System's service and technical support staff are the most experienced in the industry.







