

- 2. REMOVE AND REPLACE EXISTING CAP FLASHINGS TO FACILITATE INSTALLATION OF SHEETGOODS. FOAM ROOFING ENCAPSUATION OF EXISTING FLASHINGS AND ONTO BITUTHENE SHEETING (1 1/2" FOAM THINCKNESS ON ROOF, 1" ON VERTICAL WALLS)
- 3. BAND ALL CAP JOINTS AND TERMINATIONS WITH POLYESTER TAPE AND ROOFING COATINGS 20 MILS MINIMUM.
- 4. EXISTING SINGLE PLY ROOF SYSTEM.
- 5. TECH GUARD FOAM ROOFING SYSTEM

Products, INC. ech energy Est	WALL DETAIL (dwg. 32)	DRAWN BY:	DATE:	APPROVED:
	3003 North 73rd Street, Scottsdale, AZ 85251 402 East Grand Road, Tuscon, AZ 85705	SCALE:	PROJECT NO:	DRAWING NO.